

L111035003/McHenry County  
Catty H. D. Corporation  
ILD 180012585



# **CERCLA**

## **Screening Site Inspection Report**



**Illinois Environmental  
Protection Agency**  
P.O. Box 19276  
Springfield, IL 62794-9276

EPA Region 5 Records Ctr.



300746

## TABLE OF CONTENTS

<u>SECTION</u>		<u>PAGE</u>
1.	INTRODUCTION . . . . .	1-1
2.	SITE BACKGROUND . . . . .	2-1
2.1	INTRODUCTION . . . . .	2-1
2.2	SITE DESCRIPTION . . . . .	2-1
2.3	SITE HISTORY . . . . .	2-3
3.	SCREENING SITE INSPECTION PROCEDURES AND FIELD OBSERVATIONS . . . . .	3-1
3.1	INTRODUCTION . . . . .	3-1
3.2	SITE REPRESENTATIVE INTERVIEW . .	3-1
3.3	RECONNAISSANCE INSPECTION . . . .	3-1
3.4	SAMPLING PROCEDURES . . . . .	3-2
4.	ANALYTICAL RESULTS . . . . .	4-1
4.1	INTRODUCTION . . . . .	4-1
4.2	RESULTS OF CHEMICAL ANALYSIS OF IEPA COLLECTED SAMPLES . . . . .	4-1
5.	MIGRATION PATHWAYS . . . . .	5-1
5.1	INTRODUCTION . . . . .	5-1
5.2	GROUNDWATER . . . . .	5-1
5.3	SURFACE WATER . . . . .	5-5
5.4	AIR . . . . .	5-5
5.5	ON-SITE EXPOSURE . . . . .	5-5
6.	BIBLIOGRAPHY . . . . .	6-1

## APPENDICES

<u>APPENDIX</u>	<u>PAGE</u>
A SITE 4-MILE RADIUS MAP . . . . .	A-1
B USEPA FORM 2070-13 . . . . .	B-1
C TARGET COMPOUND LIST . . . . .	C-1
D SSI PHOTOGRAPHS . . . . .	D-1
E WELL LOGS . . . . .	E-1
F CHEMICAL ANALYSIS DATA OF IEPA COLLECTED SAMPLES . . . . .	F-1

### LIST OF ILLUSTRATIONS

<u>FIGURE</u>	<u>PAGE</u>
2-1 SITE LOCATION . . . . .	2-2
2-2 SITE FEATURES . . . . .	2-4
3-1 GROUNDWATER SAMPLE LOCATIONS . . . . .	3-3
3-2 SOIL SAMPLE LOCATIONS. . . . .	3-5
5-2 BEDROCK SURFACE MAP . . . . .	5-2
5-2 GEOLOGIC PROFILE W/ AQUIFERS . . . . .	5-4

### LIST OF TABLES

<u>TABLE</u>	<u>PAGE</u>
2-1 CHEMICALS USED IN PRODUCTION . . . . .	2-3
2-2 SITE OWNERSHIP . . . . .	2-5
3-1 LOCATION OF SAMPLED PUBLIC WELLS . . . . .	3-2
3-2 LOCATION OF SOIL SAMPLES . . . . .	3-4
4-1 RESULTS OF CHEMICAL ANALYSIS OF IEPA COLLECTED SAMPLES . . . . .	4-3

## 1. INTRODUCTION

On February 13, 1990, the Illinois Environmental Protection Agency's (IEPA's) Pre-Remedial Unit was tasked by the United States Environmental Protection Agency (USEPA) to conduct a screening site inspection (SSI) of Catty H.D. Corporation, hereafter, referred to as Catty.

IEPA initially discovered the facility in October, 1987, after finding soil contamination of alkanes, aromatics and polynuclear aromatic hydrocarbons (PNA's) between Catty's drum storage area and the village of Huntley's public well #4. Subsequently, Catty was added to CERCLIS (Comprehensive Environmental Response, Compensation and Liability Information System) by the USEPA in April of 1988. The facility was evaluated in the form of a Preliminary Assessment (PA) that was completed by Timothy Murphy of IEPA and submitted to USEPA in June of 1989. IEPA's Pre-Remedial Unit prepared a SSI work plan for Catty that was approved by USEPA in early April, 1990. The SSI was conducted on April 25, 1990 with the collection of two groundwater and six soil samples.

The purposes of an SSI have been stated by USEPA in a directive outlining Pre-Remedial program strategies. The directive states:

All sites will receive a screening SI to 1) collect additional data beyond the PA to enable a more refined preliminary HRS [Hazard Ranking System] score, 2) establish priorities among sites most likely to qualify for the NPL



[National Priorities List], and 3) identify the most critical data requirements for the listing SI step. A screening SI will not have rigorous data quality objectives (DQOs). Based on the refined preliminary HRS score and other technical judgement factors, the site will then either be designated as NFRAP [no further remedial action planned], or carried forward as an NPL listing candidate. A listing SI will not automatically be done on these site, however. First, they will go through a management evaluation to determine whether they can be addressed by another authority such as RCRA [Resource Conservation and Recovery Act]... Sites that are designated NFRAP or deferred to other statutes are not candidates for a listing SI.

The listing SI will address all the data requirements of the revised HRS using field screening and NPL level DQOs. It may also provide needed data in a format to support remedial investigation work plan development. Only sites that appear to score high enough for listing and that have not been deferred by another authority will receive a listing SI (USEPA 1988).

USEPA Region V has also instructed IEPA to identify sites during the SSI that may require removal action to remediate an immediate human health and/or environmental threat.

## 2. SITE BACKGROUND

### 2.1 INTRODUCTION


This section includes information obtained from the SSI work plan preparation.

### 2.2 SITE DESCRIPTION

Catty is located in the northwest 1/4 of Section 33, Township 43 north, Range 7 east, of the Third Principle Meridian in McHenry County, IL. Catty has the street address of 11117 South Church Street, Huntley, IL 60142. This address is in the south central part of the village of Huntley (see Figure 2-1 for site location).

The facility prints flexible labels and packaging for various uses. Catty utilizes foil, paper and some cellophane and makes laminations with wax and water base adhesives. Catty mainly supplies foil wrappings to the food industry (such as Andes Candy in WI).

The facility consists of 2.128 acres of land with several structures. The main building is a continuance of 5 brick buildings, the southern 3 having been built in 1870 and the northern 2 constructed in 1940. The total area of the main building, including the manufacturing areas, loading docks and offices, is 31,365 square feet. Located in the northwest corner of the property, is a 2,400 square feet metal building that serves as Catty's warehouse. A covered drum storage pad east of the metal warehouse, is used to store raw materials consisting mainly of solvent based inks.



Source: USGS 7.5 Min. Topo Maps - Huntley, IL Quadrangle (27B)

Figure 2-1

SITE LOCATION

The 20 feet by 20 feet brick well house on the south end of the property, is used by Catty to store drummed hazardous waste. The 67 feet 6 inch deep well inside the well house, was sealed June 23, 1988.

Catty is bordered by South Church Street and residential properties on the east, village property and Illinois Bell property on the north, Mill Street and Dean Foods to the south, and Chicago and North Western R.R. to the west. Figure 2-2 on page 2-4 shows the site features. A 4-mile radius map surrounding Catty is provided in Appendix A.

A review of Catty's Material Data Safety Sheets (MSDS) revealed the following chemicals which have been used by the facility:

Table 2-1 Chemicals Used in Production


methyl isobutyl ketone	methyl ethyl ketone (MEK)
toluene	isopropyl acetate
ethyl alcohol	isopropyl alcohol
methyl alcohol	n-propyl acetate
naphtha	ethyl acetate
2-ethoxyethanol	n-propyl alcohol
dimethyl ketone	

Wastes generated by the facility consist of waste inks mixed with ethyl alcohol, n-propyl alcohol, ethyl acetate and MEK, which are used as thinning agents. The wastes are a blend of F003, F005, and D001 substances and are generated at a rate of approximately 5 drums per month. The wastes are usually shipped every 3 months (less than 90 day storage) to EWR in Coal City, IL for incineration.


### 2.3 SITE HISTORY

The facility was first used as a dairy and creamery.

Figure 2-2



Scale 1 inch = 70 feet



SITE FEATURES

Sometime between the years of 1907 and 1946, the property was reverted to a brewery and then to a manufacturer of gaskets by Fenc1. In 1946, the facility started printing flexible packaging materials and has continued these operations ever since. The legal owners of Catty have been and are as follows:

Table 2-2 Site Ownership

?	- 1946	Fenc1
1946	- 1964	the Catty family
1964	- 10/17/1983	the Krug family
10/17/1983	- 05/02/1986	International Foils, Inc.
05/02/1986	- 12/31/1986	Rostra Holdings, Inc. (Ohio)
12/31/1986	- 02/10/1987	Rust Ventures L.P.
		Walter Rose
		John Strautnieks
		Joseph Aragona
		William McCuster
02/10/1987	- Present	Catty Corporation
		Raymond G. Scott

North of Catty's drum storage area, village workers were trenching a line to repair a broken valve for well #4 (10/08/87), when they discovered soil contamination. Strong solvent odors and soil discoloration were observed within 15 feet of Catty's property. Sampling revealed 13 volatile compounds in the range of 2.4 to 13.2 ug/g (ppm). At the time of the trenching, Catty's drum storage area consisted of a wooden planked floor and included storage for the drums that contained the facility's waste streams. Spills and overturned drums were photographed by village workers during this time. Later, in May of 1988, soil gas readings were obtained which showed the greatest contamination nearest the fence next to the drum storage area. A sample collected at

this spot from one foot above the water table (6 feet water table) showed 6 PNA's in the range of 7.6 to 133 ug/g.

### 3. SCREENING SITE INSPECTION PROCEDURES AND FIELD OBSERVATIONS

#### 3.1 INTRODUCTION

This section outlines procedures and observations of the SSI at Catty. Individual subsections address the site representative interview, reconnaissance inspection and sampling procedures. The SSI was conducted in accordance with the USEPA-approved work plan.

The USEPA Potential Hazardous Waste Site Inspection Report (Form 2070-13) for Catty is located in Appendix B.

#### 3.2 SITE REPRESENTATIVE INTERVIEW

Facility representatives for Catty included President and owner Raymond Scott and Purchasing Agent Gene Konaszewski, who has worked there 23 years. The interview took place during the reconnaissance inspection that was conducted on April 4, 1990. The discussions centered on the IEPA's Pre-Remedial process, the possible sample locations and the history of the facility.

#### 3.3 RECONNAISSANCE INSPECTION

After the interview, IEPA personnel conducted a reconnaissance inspection of Catty and the surrounding area. The inspection included a walk around Catty to identify potential sampling locations, measure and identify appropriate health and safety requirements. Village employees were also contacted to secure groundwater sampling points, well #4 and well #6.

Reconnaissance Inspection Observations. The drum



storage pad that had been installed in November of 1987, appeared in sound condition. Spills and staining around the outside edge of the pad was not evidenced by IEPA personnel.

### 3.4 SAMPLING PROCEDURES

Samples were collected by IEPA personnel following procedures outlined in IEPA's Pre-Remedial Quality Assurance Project Plan and Standard Operating Procedures (QAPP and SOP's are approved and on file with the USEPA). The samples were collected to determine levels of USEPA Target Compound List (TCL) compounds present at the site. The TCL is provided in Appendix C.

Groundwater Sampling Procedures. On April 25, 1990 IEPA personnel collected two groundwater samples. Figure 3-1 on page 3-3 shows the 2 public well sample locations. G501 was obtained from the nearby Huntley well #4 and G502 was taken as background from Huntley well #6, nine tenths of a mile south of the site. Well logs for both wells are included in Appendix E.


Table 3-1 Location of Sampled Public Wells

<u>Sample</u>	<u>Depth</u>	<u>Aquifer</u>	<u>Location</u>	<u>Time</u>
G501	63'	S+G	Well #4, 20' SW of water tower	1:00p
G502	154'	S+G	Well #6, N side of Kreutzer Rd. E of Rt. 47	1:50p

N - north, E - east, W - west, S - south, S+G - sand and gravel, and ' - feet

Sample G501 was obtained from a raw faucet tap inside the #4 pump house after letting the well pump 30 minutes at a rate of 285 gallons per minute. Well #6 had been pumping

Figure 3-1



throughout the day and did not need to be purged. The sample G502, was also collected via raw facet tap from inside the #6 well house. Neither sample was field filtered for metals.


Soil Sampling Procedures. During the SSI, IEPA personnel also collected six soil samples. Figure 3-2 on page 3-5 shows the six soil sample locations. An off-site soil sample, X107, was collected as a background sample to compare with the on-site soil samples.

Table 3-2 Soil Sampling Locations


<u>Sample</u>	<u>Depth</u>	<u>Location</u>	<u>Time</u>
X101	3.0-4.0'	Center of N side of Drum Pad	5:00p
X102	4.0-6.0'	Center of E side of Drum Pad	3:30p
X103	3.0-3.5'	Center of S side of Drum Pad angled to get under Pad	2:50p
X104	4.0-5.0'	Center of W side of Drum Pad	4:15p
X105	3.5-4.5'	20' S of Metal Bldg 6' E of fence	5:30p
X106	2.5' auger refusal	Did not collect sample on N side of Brick Bldg.	----
X107	4.0-5.0'	24' E & 3' N of utility pole 2' E of Rd.	12:30p

The soil samples were collected with stainless steel bucket augers. The soil was transferred directly into the sample jars from the sampling device. The soil and groundwater sample jars were evidence taped and packaged in accordance with USEPA required procedures. The IEPA samples were analyzed for the TCL by IEPA's Springfield lab (organic analysis) and IEPA's Champaign lab (inorganic analysis). Photographs for the Catty SSI are provided in Appendix D.

Figure 3-2



Scale 1 inch = 70 feet



Decontamination Procedures. Standard IEPA

decontamination procedures were followed prior to the collection of all samples. The procedures included the scrubbing of all equipment (augers, spoons, pans, etc.) with a non-foaming Trisodium Phosphate solution, rinsing with hot tap water, rinsing with acetone, rinsing with hot tap water again and final rinsed with distilled water. All equipment is air dried, then wrapped and stored in heavy duty aluminum foil for transport to the field. Field decontamination procedures include all of the above except the hot tap water rinse.

## 4. ANALYTICAL RESULTS

### 4.1 INTRODUCTION

This section includes the analytical results of Target Compound List compounds from IEPA collected samples at Catty.

### 4.2 ANALYTICAL RESULTS FROM IEPA COLLECTED SAMPLES

Chemical analysis of the 2 groundwater samples collected by IEPA personnel revealed the following substances: inorganics and common groundwater constituents. Analysis of 6 soil samples collected by IEPA personnel revealed the following substances: volatiles, inorganics, common laboratory artifacts and common soil constituents (see Table 4-1 for the summary of groundwater and soil results). Complete laboratory analytical data for the groundwater and soil samples are provided in Appendix F.

The groundwater samples did not appear to be effected by the contamination found in the soil. Well #4 (G501) had low levels of sulfates (below Proposed Maximum Contaminant Levels) and well #6 had 201 ug/l (ppb) arsenic.

In the soil samples, the highest concentrations of contaminants were detected in samples X101 and X102 on the north and east sides of the pad respectively. Three polynuclear aromatic hydrocarbons (PNA's) were detected in X101, along with bis(2-ethylhexyl)phthalate. The phthalate was also found in two other on-site samples, the highest concentration being found in X103 at 1400 ug/kg (ppb). The PNA, pentachlorophenol (PCP), appeared as the highest

concentration of any semi-volatile contaminant found. PCP at 5600 ug/kg was detected only in sample X101.

Volatiles were also found in all of the on-site soil samples. The highest concentration of a volatile was xylene at 5800 ug/kg in sample X101. Xylene was found in every one of the on-site soil samples. Ethylbenzene was found in four of the on-site samples in a range of an estimated value of 2 ug/kg to 280 ug/kg. Toluene was found above background in X101 and X102. X102 also had several compounds not found in the other samples including trichloroethene estimated at 6 ug/kg, 2-hexanone at 10 ug/kg, carbon disulfide estimated at 1 ug/kg and 1,1-dichloroethane estimated at 0.5 ug/kg.

CATTY CORPORATION  
ILD 180012585

TABLE 4-1

SAMPLING POINT  
PARAMETER

VOLATILES (ppb)

Acetone	--	--	--	470	E	--	110	--	70	--
Carbon Disulfide	--	--	--	1	J	--	--	--	--	--
1,1-Dichloroethane	--	--	--	0.5	J	--	--	--	--	--
2-Butanone (MEK)	10	R	10	R	120	R	11	R	12	R
Trichloroethene	--	--	--	6	J	--	--	--	--	--
2-Hexanone	--	--	--	10	--	--	--	--	--	--
Toluene	--	--	--	140	J	--	--	--	0.4	J
Ethylbenzene	--	--	--	280	J	8	2	J	--	--
Xylene(total)	--	--	--	5800	140	230	8	1	J	--

SEMI-VOLATILES (ppb)

Naphthalene	--	--	--	1100	--	--	--	--	--	--
2-Methylnaphthalene	--	--	--	1600	--	--	--	--	--	--
Pentachlorophenol	--	--	--	5600	--	--	--	--	--	--
bis(2-Ethylhexyl)phthalate	--	--	--	190	J	400	J	1400	--	--

INORGANICS (water-ppb, soil-ppm)

Aluminum	--	--	--	8260	5590	5240	9400	7800	4700	--
Antimony	--	--	--	0.9	B	--	--	--	--	--
Arsenic	1.0	B	12	12	2.1	4.7	2.1	B	2.8	B
Barium	--	--	201	107	49	46	78	71	27	B
Beryllium	--	--	--	0.8	B	0.4	B	0.6	B	0.4
Cadmium	--	--	--	0.9	B	0.5	B	--	--	--
Calcium	128000.0	69500	--	12600	19000	51800	2300	10400	90200	--
Chromium	--	--	--	13	9.1	11	13	13	9.1	--
Cobalt	--	--	--	6.1	B	3.8	B	6	B	2.8
Copper	2.6	B	--	35	127	12	17	16	11	--
Iron	1980	2300	--	12700	10600	12500	14200	17500	9300	--
Lead	2	B	--	118	20	6.0	36	4.5	4.3	--
Magnesium	57900	39000	--	6440	11200	31100	4500	7900	29200	--
Manganese	80	18	--	260	210	410	155	490	178	--
Mercury	--	--	--	0.4	--	--	0.11	--	--	--
Nickel	--	--	--	15	9.5	11	12	17	8.7	--
Potassium	2310	B	--	--	--	--	--	--	--	--
Selenium	--	--	--	--	0.3	B	--	--	--	--
Silver	--	--	--	--	--	--	--	--	--	--
Sodium	12700	11000	--	99	B	46	B	38	B	33
Thallium	--	--	--	0.2	B	0.1	B	0.3	B	0.2
Vanadium	--	--	--	20	19	18	23	22	13	--
Zinc	--	--	--	330	33	23	61	34	72	--
Cyanide	--	--	--	--	--	--	--	--	--	--
Sulfate	145000.0	--	--	--	--	--	--	--	--	--
Sulfide	--	--	--	--	--	--	--	--	--	--
TEMPERATURE	49.5	--	--	--	--	--	--	--	--	--
SP. COND. (umhos)	960	--	--	--	--	--	--	--	--	--
PH	--	--	--	--	--	--	--	--	--	--

meter broke



# U.S.E.P.A. DEFINED DATA QUALIFIERS

## QUALIFIER      DEFINITION ORGANICS

- U      Compound was tested for but not detected. The sample quantitation limit must be corrected for dilution and for percent moisture. For soil samples subjected to GPC clean-up procedures, the CRQL is also multiplied by two, to account for the fact that only half of the extract is recovered.
  
- J      Estimated value. Used when estimating a concentration for tentatively identified compounds (TICs) where a 1:1 response is assumed or when the mass spectral data indicate the presence of a compound that meets the identification criteria and the result is less than the sample quantitation limit but greater than zero. Used in data validation when the quality control data indicate that a value may not be accurate.
  
- C      This flag applies to pesticide results where the identification is confirmed by GC/MS.
  
- B      Analyte was found in the associated blank as well as in the sample. It indicates possible/probable blank contamination and warns the data user to take appropriate action
  
- D      Identifies all compounds identified in an analysis at a secondary dilution factor. If a sample or extract is re-analyzed at a higher dilution factor as in the "E" flag above, the "DL" suffix is appended to the sample number on the Form I for the diluted sample, and all concentration values are flagged with the "D" flag.

## DEFINITION INORGANICS

- Analyte was analyzed for but not detected.
- Estimated value. Used in data validation when the quality control data indicate that a value may not be accurate.
- Method qualifier indicates analysis by the Manual Spectrophotometric method.
- The reported value is less than the CRDL but greater than the instrument detection limit (IDL).
- not used

QUALIFIERDEFINITION ORGANICSDEFINITION INORGANICS

- E Identifies compounds whose concentrations exceed the calibration range for that specific analysis. All extracts containing compounds exceeding the calibration range must be diluted and analyzed again. If the dilution of the extract causes any compounds identified in the first analysis to be below the calibration range in the second analysis, then the results of both analyses must be reported on separate Forms I. The Form I for the diluted sample must have the "DL" suffix appended to the sample number.

The reported value is estimated because of the presence of interference

- A This flag indicates that a TIC is a suspected aldol concentration product formed by the reaction of the solvents used to process the sample in the laboratory.

Method qualifier indicates analysis by Flame Atomic Absorption (AA).

- M not used

Duplicate injection (a QC parameter) not met.

- N not used

Spiked sample (a QC parameter) recovery not within control limits.

- S not used

The reported value was determined by the Method of Standard Additions (MSA).

- W not used

Post digestion spike for Furnace AA analysis (a QC parameter) is out of control limits of 85% to 115% recovery, while sample absorbance is less than 50% of spike absorbance.

- \* not used

Duplicate analysis (a QC parameter) not within control limits.

- + not used

Correlation coefficient for MSA (a QC parameter) is less than 0.995.

QUALIFIER      DEFINITION ORGANICS

- P            not used
- CV          not used
- AV          not used
- AS          not used
- T            not used
- NR          The analyte was not required to  
                be analyzed.
- R            Rejected data. The QC  
                parameters indicate that the  
                data is not usable for any  
                purpose.

DEFINITION INORGANICS

- Method qualifier indicates analysis  
by ICP (Inductively Coupled  
Plasma) Spectroscopy.
- Method qualifier indicates analysis  
by Cold Vapor AA.
- Method qualifier indicates analysis  
by Automated Cold Vapor AA
- Method qualifier indicates analysis  
by Semi-Automated Cold  
Spectrophotometry.
- Method qualifier indicates  
Titrimetric analysis.
- The analyte was not required to be  
analyzed.
- Rejected data. The QC parameters  
indicate that the data is not usable  
for any purpose.

## 5. DISCUSSION OF MIGRATION PATHWAYS

### 5.1 INTRODUCTION

This section discusses data and information that apply to potential migration pathways and targets of TCL compounds that may be attributable to Catty.

The four migration pathways of concern are groundwater, surface water, air and on-site exposure.


### 5.2 GROUNDWATER

Sand and gravel deposits are present within the glacial drift at most sites in McHenry County and offer possibilities for the development of moderate to large quantities of water from individual wells. These Pleistocene series sands and gravels are the primary source of most public and private water supplies throughout the county (Illinois State Water Survey (ISWS) Bulletin 60-19) and constitute the aquifer of concern. According to area ISWS well logs, the drift averages approximately 200 feet in thickness.




The Maquoketa Group underlies the glacial drift at in the Huntley area and consists primarily of non-water bearing shales that separate the Silurian aquifer from deeper water-bearing units. Figure 5-1 is a bedrock surface map of McHenry and Kane Counties. A 3-mile circle is drawn around the site showing the Maquoketa Group as the uppermost bedrock unit in the area.

Below the Maquoketa Group is the Cambrian-Ordovician aquifer system consisting of the hydraulically connected

Figure 5-1



EXPLANATION

-  Silurian System
-  Maquoketa Group
-  Galena and Platteville Dolomite Groups

Areal geology of the bedrock surface

(Modified from *Geologic Map of Illinois*, Willman and others, 1967)

Galena-Platteville Dolomite, Glenwood-St. Peter Sandstone, Eminence-Potosi Dolomite, Franconia Formation, and Ironton-Galesville Sandstone (ISWS Bulletins 60-19 and 60-22).








Figure 5-2 is a geologic profile showing the aquifers in McHenry County.

Groundwater samples collected during the April 25, 1990 SSI, indicate that neither the nearby public well #4, 15 feet away, nor public well #6, nine tenths of a mile south, are currently being affected by the soil contamination at Catty. According to IEPA Division of Public Water Supplies, only one other public well is located within four miles of the site. That well is Huntley well #5, also finished in sands and gravels at a depth of 95 feet and is located seven tenths of a mile north of Catty. The 3 village of Huntley wells supply 1646 residents with drinking water.

Many private wells within three miles obtain water from the shallow sand and gravel deposits of the glacial till, which has been designated as the aquifer of concern. Approximately 60 wells (serving 179 people) use the shallow aquifer and about 43 wells (serving 128 people) use the bedrock aquifer (Illinois State Geological Survey well logs, 1980 McHenry County Census Data - 2.99 persons per household). Based on a house count from 1972 revised US Geological Survey (USGS) 7.5 minute quadrangle topographic maps, 131 homes within 3 miles would require a water well (serving 391 people).

The nearest private well, as determined by the

Figure 5-2

SYSTEM	SERIES	GROUP OR FORMATION	AQUIFER	LOG	THICKNESS (FT)	DESCRIPTION	
QUATERNARY	PLEISTOCENE		Sands and Gravels		0-470	Unconsolidated glacial deposits-pebbly clay (till), silt, sand and gravel Alluvial silts and sands along streams	
		Fissure Fillings			Shale, sandy, brown to black		
SILURIAN	NIAGARAN	Racine	Silurian		0-90	Dolomite, very pure to argillaceous, silty, cherty; reefs in upper part	
		Sugar Run				Dolomite, slightly argillaceous and silty	
		Joliet				Dolomite, very pure to shaly and shale, dolomitic; white, light gray, green, pink, maroon	
	ALEXANDRIAN	Kankakee			0-70	Dolomite, pure top 1'-2', thin green shale partings, base glauconitic	
		Elwood				Dolomite, slightly argillaceous, abundant layered white chert	
		Wilhelmi				Dolomite, gray, argillaceous and becomes dolomitic shale at base	
ORDOVICIAN	CINCINNATIAN	Maquoketa			0-210	Shale, red to maroon, oolites Shale, silty, dolomitic, greenish gray, weak (Upper unit) Dolomite and limestone, white, light gray, interbedded shale (Middle unit) Shale, dolomitic, brown, gray (Lower unit)	
	CHAMPLAINIAN	Galena	Galena-Platteville		290-335	Dolomite, and/or limestone, cherty (Lower part)	
		Platteville				Dolomite, shale partings, speckled	
		Glenwood	Glenwood-St. Peter		160-280	Dolomite and/or limestone, cherty, sandy at base	
		St. Peter				Sandstone, fine and coarse grained; little dolomite; shale at top Sandstone, fine to medium grained; locally cherty red shale at base	
	CAMBRIAN	CROIXAN	Eminence	Eminence-Potosi		0-150	Dolomite, light colored, sandy, thin sandstones
Potosi			Dolomite, fine-grained, gray to brown, drusy quartz				
Franconia			Franconia	40-95		Dolomite, sandstone and shale, glauconitic, green to red, micaceous	
Ironton			Ironton-Galesville	100-190		Sandstone, fine to coarse grained, well sorted; upper part dolomitic	
Galesville							
Eau Claire				385-485		Shale and siltstone, dolomitic, glauconitic; sandstone, dolomitic, glauconitic	
Elmhurst Member			Elmhurst-Mt. Simon			1200-2000	Sandstone, coarse grained, white, red in lower half; lenses of shale and siltstone, red, micaceous
Mt. Simon							
PRE-CAMBRIAN						Granitic rocks	

Generalized column of rock stratigraphic units and aquifers in McHenry County

(Prepared by M. L. Sargent, Illinois State Geological Survey)

reconnaissance visit, using the aquifer of concern (sand and gravel deposits) is 1/4 mile north of the site (see Appendix E for well logs). Groundwater is encountered at a depth of 6 feet however flow direction is unknown.

### 5.3 SURFACE WATER

Due to little topographic relief, drainage at the site would not effect any surface water. The nearest surface water is the South Branch Kishwaukee River, three quarters of a mile south of the site. The South Branch flows northwest to the Kishwaukee River. Between the site and the South Branch, is a wetland area greater than 5 acres.

### 5.4 AIR

No documented releases to the air were observed during the SSI. A photo-ionization detector (HNU) with an 11.7 eV lamp was used to screen the monitor well head space and soil samples. On sample X107, the HNU rose to 15 meter units above background and then returned to normal.

### 5.5 ON-SITE EXPOSURE

The site is not completely fenced, however the drum storage pad is fenced and locked. The nearest residence is just across South Church Street.

Approximately 1678 people live within a 1 mile radius of the site.



## 6. BIBLIOGRAPHY

Illinois Department of Energy and Natural Resources, State Water Survey, water well records of wells in McHenry County, T.43N. R.7E., T.43N. R.6E. and T.43N. R.8E. , and in Kane County, T.42N. R.7E., T.42N. R.6E. and T.42N. R.3E.

Illinois Department of Energy and Natural Resources, State Water Survey. 1978, Public Groundwater Supplies for Kane County. Bulletin 60-22, Urbana, IL.

Illinois Department of Energy and Natural Resources, State Water Survey. 1976, Public Groundwater Supplies for McHenry County. Bulletin 60-19, Urbana, IL.

Illinois Environmental Protection Agency, 1984, Potential Hazardous Waste Site Preliminary Assessment for Catty H. D. Corporation, ILD180012585, prepared by Timothy J. Murphy, Springfield, IL.

Illinois Environmental Protection Agency, Division of Land Pollution Control file 1110355003.

Illinois Environmental Protection Agency Division of Public Water Supplies, file for Huntley Public Water Supply System.

USEPA, Office of Solid Waste and Emergency Response, February 12, 1988, Pre-Remedial Strategy for Implementing SARA, Directive number 9345.2-01, Washington, D.C.

USGS, 7.5 Minute Series Quadrangle Topographic Maps: 1975, Marengo South, IL (26A), 1972; Huntley, IL. (27B), 1968, Hampshire, IL (26D); 1980, Crystal Lake, IL (27A); 1972, Pingree Grove, IL (27C); 1980, Elgin, IL (27D).

**APPENDIX A**  
**4-MILE RADIUS MAP**

# SDMS US EPA Region V

## Imagery Insert Form

**Some images in this document may be illegible or unavailable in SDMS.  
Please see reason(s) indicated below:**

Illegible due to bad source documents. Image(s) in SDMS is equivalent to hard copy.

**Specify Type of Document(s) / Comments:**

Includes \_\_\_ COLOR or RESOLUTION variations.

Unless otherwise noted, these pages are available in monochrome. The source document page(s) is more legible than the images. The original document is available for viewing at the Superfund Records Center.

**Specify Type of Document(s) / Comments:**

Confidential Business Information (CBI).

This document contains highly sensitive information. Due to confidentiality, materials with such information are not available in SDMS. You may contact the EPA Superfund Records Manager if you wish to view this document.

**Specify Type of Document(s) / Comments:**

x

Unscannable Material:

Oversized \_\_\_x\_\_\_ or \_\_\_ Format.

Due to certain scanning equipment capability limitations, the document page(s) is not available in SDMS.

**Specify Type of Document(s) / Comments:**

USGS TOPOGRAPHIC MAP

Document is available at the EPA Region 5 Records Center.

**Specify Type of Document(s) / Comments:**

**APPENDIX B**

**USEPA 2070-13 FORM**



# Site Inspection Report



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
1LD 180012585

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site) Catty Corporation		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER 11117 South Church Street				
03 CITY Huntley		04 STATE IL	05 ZIP CODE 60142	06 COUNTY McHenry	07 COUNTY CODE 111	08 CONG DIST 12
09 COORDINATES LATITUDE 42 10 00.0		LONGITUDE 088 25 32.0				
10 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER <input type="checkbox"/> G. UNKNOWN						

III. INSPECTION INFORMATION

01 DATE OF INSPECTION 04, 25 90 MONTH DAY YEAR	02 SITE STATUS <input checked="" type="checkbox"/> ACTIVE <input type="checkbox"/> INACTIVE	03 YEARS OF OPERATION 1907 Present BEGINNING YEAR ENDING YEAR
--	---	---

04 AGENCY PERFORMING INSPECTION (Check all that apply)

<input type="checkbox"/> A. EPA	<input type="checkbox"/> B. EPA CONTRACTOR	<input type="checkbox"/> C. MUNICIPAL	<input type="checkbox"/> D. MUNICIPAL CONTRACTOR
<input checked="" type="checkbox"/> E. STATE	<input type="checkbox"/> F. STATE CONTRACTOR	<input type="checkbox"/> G. OTHER	

(Name of firm) (Name of firm) (Specify)

05 CHIEF INSPECTOR Timothy J. Murphy	06 TITLE Environmental Protection Specialist	07 ORGANIZATION IEPA	08 TELEPHONE NO. (217) 782-6760
09 OTHER INSPECTORS Greg DUNN	10 TITLE "	11 ORGANIZATION "	12 TELEPHONE NO. ( ) "
			( )
			( )
			( )
			( )

13 SITE REPRESENTATIVES INTERVIEWED Raymond Scott	14 TITLE President Owner	15 ADDRESS Same as 02 above	16 TELEPHONE NO. ( )
Gene Konaszewski	Purchasing Agent (of 23,125)	"	( )
			( )
			( )
			( )
			( )

17 ACCESS GAINED BY (Check one) <input checked="" type="checkbox"/> PERMISSION <input type="checkbox"/> WARRANT	18 TIME OF INSPECTION	19 WEATHER CONDITIONS Sunny Mild high 70 <sup>3</sup> °F
---	-----------------------	---

IV. INFORMATION AVAILABLE FROM

01 CONTACT Gene Konaszewski	02 OF (Agency/Organization) Catty Corporations	03 TELEPHONE NO. (708) 669-3860		
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM Timothy J. Murphy	05 AGENCY IEPA	06 ORGANIZATION RPMS	07 TELEPHONE NO. (217) 785-5737	08 DATE 09, 19, 90 MONTH DAY YEAR

[illegible]

## EPA FORM 2070-13 (7-81)



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
14D 180012585

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION

03 POPULATION POTENTIALLY AFFECTED: 1825

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

04 NARRATIVE DESCRIPTION

☒ POTENTIAL

☐ ALLEGED

Vadose zone soil samples from adjacent property show semi-volatile organic compounds. On-site samples contain the same contaminants in the soil up to 6 feet below the surface near the water table

01 ☐ B. SURFACE WATER CONTAMINATION

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

Nearest surface water is .75 mile south of site

01 ☒ C. CONTAMINATION OF AIR

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

04 NARRATIVE DESCRIPTION

☒ POTENTIAL

☐ ALLEGED

up, Soil gas readings showed contamination that may have contributed to an air release (05/03/90). However, readings taken after the city's property was excavated and removed showed NO breathing zone threat with the HNU during the 04/25/90 SSI.

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

None documented or observed

01 ☐ E. DIRECT CONTACT

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

None documented or observed

01 ☒ F. CONTAMINATION OF SOIL

03 AREA POTENTIALLY AFFECTED:  $\approx 2$   
(Acres)

02 ☒ OBSERVED (DATE: 04/25/90)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

Soil samples near the newly constructed drum storage pad show PNA's and several volatiles from the samples collected during the SSI

01 ☒ G. DRINKING WATER CONTAMINATION

03 POPULATION POTENTIALLY AFFECTED: 1825

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

04 NARRATIVE DESCRIPTION

☒ POTENTIAL

☐ ALLEGED

see A. above

Huntley Well # 4 is 15' from Catty's drum pad, the well is 63 feet deep.

01 ☐ H. WORKER EXPOSURE/INJURY

03 WORKERS POTENTIALLY AFFECTED: \_\_\_\_\_

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

None documented or observed

01 ☐ I. POPULATION EXPOSURE/INJURY

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

04 NARRATIVE DESCRIPTION

☐ POTENTIAL

☐ ALLEGED

see G. above





POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
ILD 180012585

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

None documented or observed

01 ☐ K. DAMAGE TO FAUNA

04 NARRATIVE DESCRIPTION (include name(s) of species)

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

None documented or observed

01 ☐ L. CONTAMINATION OF FOOD CHAIN  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

None documented or observed

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES

(Spills/Runoff/ Standing liquids, Leaking drums)

03 POPULATION POTENTIALLY AFFECTED: 1825

02 ☒ OBSERVED (DATE: 10/08/87)

☐ POTENTIAL

☐ ALLEGED

04 NARRATIVE DESCRIPTION

Wastes were stored on wooden planked pad without secondary containment  
Wastes were stored in a well house prior to plugging the shallow well.

01 ☒ N. DAMAGE TO OFFSITE PROPERTY  
04 NARRATIVE DESCRIPTION

02 ☒ OBSERVED (DATE: 10/08/87)

☐ POTENTIAL

☐ ALLEGED

Contamination was first found on the adjacent village property next to Catty's drum storage area

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

None documented or observed

01 ☒ P. ILLEGAL/UNAUTHORIZED DUMPING  
04 NARRATIVE DESCRIPTION

02 ☒ OBSERVED (DATE: 10/08/87)

☐ POTENTIAL

☐ ALLEGED

Drums with tops removed, overturned drums and spills were photographed by a village consultant at the drum storage area, prior to the new pad being built

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

III. TOTAL POPULATION POTENTIALLY AFFECTED: 1825

IV. COMMENTS

V. SOURCES OF INFORMATION (Cite specific references, e.g. state files, sample analysis reports)

EPA DLPC file # 1110355003



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION  
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
1LD 180012585

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A. NPDES				
<input type="checkbox"/> B. UIC				
<input type="checkbox"/> C. AIR				
<input checked="" type="checkbox"/> D. RCRA				less than 90 storage
<input type="checkbox"/> E. RCRA INTERIM STATUS				
<input type="checkbox"/> F. SPCC PLAN				
<input type="checkbox"/> G. STATE (Specify)				
<input type="checkbox"/> H. LOCAL (Specify)				
<input type="checkbox"/> I. OTHER (Specify)				
<input type="checkbox"/> J. NONE				

III. SITE DESCRIPTION

01 STORAGE/DISPOSAL (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT (Check all that apply)	05 OTHER
<input type="checkbox"/> A. SURFACE IMPOUNDMENT			<input type="checkbox"/> A. INCINERATION	<input checked="" type="checkbox"/> A. BUILDINGS ON SITE
<input type="checkbox"/> B. PILES			<input type="checkbox"/> B. UNDERGROUND INJECTION	4
<input checked="" type="checkbox"/> C. DRUMS, ABOVE GROUND	5-55gal	per month	<input type="checkbox"/> C. CHEMICAL/PHYSICAL	
<input type="checkbox"/> D. TANK, ABOVE GROUND			<input type="checkbox"/> D. BIOLOGICAL	
<input type="checkbox"/> E. TANK, BELOW GROUND			<input type="checkbox"/> E. WASTE OIL PROCESSING	
<input type="checkbox"/> F. LANDFILL			<input type="checkbox"/> F. SOLVENT RECOVERY	
<input type="checkbox"/> G. LANDFARM			<input type="checkbox"/> G. OTHER RECYCLING/RECOVERY	
<input type="checkbox"/> H. OPEN DUMP			<input type="checkbox"/> H. OTHER (Specify)	
<input type="checkbox"/> I. OTHER (Specify)				06 AREA OF SITE 2.128 (Acres)

07 COMMENTS Waste  
drums are stored in 20x20 well house at South end of Property  
Production materials are stored in drums at the newly constructed (Nov '87)  
drum pad

IV. CONTAINMENT

01 CONTAINMENT OF WASTES (Check one)  
☒ A. ADEQUATE, SECURE ☐ B. MODERATE ☐ C. INADEQUATE, POOR ☐ D. INSECURE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC.

Currently, containment is Secure, but prior to November 1987, wastes and production materials were stored on a wooden planked pad. For a while, waste were stored Next to a well in the well house

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE: ☐ YES ☒ NO  
02 COMMENTS

VI. SOURCES OF INFORMATION (Cite specific references, e.g. state files, sample analysis, reports)

EPA DLPC file # L1110355003



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
LD 180012585

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY  
(Check as applicable)

SURFACE

WELL

02 STATUS

ENDANGERED

AFFECTED

MONITORED

03 DISTANCE TO SITE

COMMUNITY

A. ☐

B. ☒

A. ☒

B. ☐

C. ☐

A. .00018 (mi)

NON-COMMUNITY

C. ☐

D. ☒

D. ☒

E. ☐

F. ☐

B. .25 (mi)

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (Check one)

☒ A. ONLY SOURCE FOR DRINKING

☐ B. DRINKING  
(Other sources available)

☐ C. COMMERCIAL, INDUSTRIAL, IRRIGATION  
(Limited other sources available)

☐ D. NOT USED, UNUSEABLE

COMMERCIAL, INDUSTRIAL, IRRIGATION  
(No other water sources available)

02 POPULATION SERVED BY GROUND WATER 1825

03 DISTANCE TO NEAREST DRINKING WATER WELL .00018 (mi)

04 DEPTH TO GROUNDWATER

6 (ft)

05 DIRECTION OF GROUNDWATER FLOW

UNKNOWN

06 DEPTH TO AQUIFER  
OF CONCERN

6 (ft)

07 POTENTIAL YIELD  
OF AQUIFER

UNKNOWN (gpd)

08 SOLE SOURCE AQUIFER

☐ YES ☒ NO

09 DESCRIPTION OF WELLS (including usage, depth, and location relative to population and buildings)

Well #4 (Huntley) 63' deep 15' North of drum storage pad screened in sands of gravels of glacial tills

10 RECHARGE AREA

☒ YES

☐ NO

COMMENTS infiltration of rain water

11 DISCHARGE AREA

☐ YES

☒ NO

COMMENTS

IV. SURFACE WATER

01 SURFACE WATER USE (Check one)

☐ A. RESERVOIR, RECREATION  
DRINKING WATER SOURCE

☐ B. IRRIGATION, ECONOMICALLY  
IMPORTANT RESOURCES

☐ C. COMMERCIAL, INDUSTRIAL

☐ D. NOT CURRENTLY USED

02 AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER

NAME:

AFFECTED

DISTANCE TO SITE

South Branch Kishwaukee River

☐

.75 (mi)

☐

(mi)

☐

(mi)

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN

2.99/household

McHenry Co. Census

02 DISTANCE TO NEAREST POPULATION

ONE (1) MILE OF SITE

TWO (2) MILES OF SITE

THREE (3) MILES OF SITE

A. 1678  
NO. OF PERSONS

B. 1812  
NO. OF PERSONS

C. 2036  
NO. OF PERSONS

.0094 (mi)

03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE

2650

04 DISTANCE TO NEAREST OFF-SITE BUILDING

.0094 (mi)

05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site, e.g., rural, village, densely populated urban area)

Cathy is located in the south central part of the village of Huntley, IL, outside the village, the rural population is spread out



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE IL 02 SITE NUMBER 180012585

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (Check one)

☐ A.  $10^{-6} - 10^{-8}$  cm/sec ☒ B.  $10^{-4} - 10^{-6}$  cm/sec ☐ C.  $10^{-4} - 10^{-3}$  cm/sec ☐ D. GREATER THAN  $10^{-3}$  cm/sec

02 PERMEABILITY OF BEDROCK (Check one)

☒ A. IMPERMEABLE (Less than  $10^{-6}$  cm/sec) ☐ B. RELATIVELY IMPERMEABLE ( $10^{-4} - 10^{-6}$  cm/sec) ☐ C. RELATIVELY PERMEABLE ( $10^{-2} - 10^{-4}$  cm/sec) ☐ D. VERY PERMEABLE (Greater than  $10^{-2}$  cm/sec)

03 DEPTH TO BEDROCK

200 (ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

6 (ft)

05 SOIL pH

UNKNOWN

06 NET PRECIPITATION

32 (in)

07 ONE YEAR 24 HOUR RAINFALL

2.5 (in)

08 SLOPE  
SITE SLOPE

< 3 %

DIRECTION OF SITE SLOPE

SW

TERRAIN AVERAGE SLOPE

< 3 %

09 FLOOD POTENTIAL

SITE IS IN N/A YEAR FLOODPLAIN

10

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

ESTUARINE

OTHER

A. \_\_\_\_\_ (mi)

B. .15 (mi)

12 DISTANCE TO CRITICAL HABITAT (of endangered species)

ENDANGERED SPECIES: N/A

13 LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL

RESIDENTIAL AREAS; NATIONAL/STATE PARKS,  
FORESTS, OR WILDLIFE RESERVES


AGRICULTURAL LANDS  
PRIME AG LAND AG LAND

A. .0094 (mi)

B. .0094 (mi)

C. \_\_\_\_\_ (mi) D. .50 (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY



VII. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

USGS 7.5 Min. Topographic Series Huntley, IL (27B)  
HRS Users Manual for precipitation data



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 6 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
1LD 180012585

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER	2	IEPA organics lab - Springfield, IL IEPA inorganics lab - Champaign, IL	6/25/90
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
SPILL			
SOIL	6	11	11
VEGETATION			
OTHER			

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS
Distance Measurements	for soil samples

IV. PHOTOGRAPHS AND MAPS

01 TYPE <input checked="" type="checkbox"/> GROUND <input type="checkbox"/> AERIAL	02 IN CUSTODY OF <u>USEPA in SSI Report, IEPA</u> <small>(Name of organization or individual)</small>
03 MAPS <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS <u>with SSI report</u>

V. OTHER FIELD DATA COLLECTED (Provide narrative description)

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis reports)

IEPA Work Plan for Catty Corporation  
IEPA SSI 04/25/90



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 7 - OWNER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
1LD 180012585

II. CURRENT OWNER(S)

PARENT COMPANY (if applicable)

01 NAME Raymond Scott			02 D+B NUMBER			08 NAME N/A			09 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 1117 S. Church St			04 SIC CODE			10 STREET ADDRESS (P.O. Box, RFD #, etc.)			11 SIC CODE								
05 CITY Huntley			06 STATE IL			07 ZIP CODE 60142			12 CITY			13 STATE			14 ZIP CODE		
01 NAME			02 D+B NUMBER			08 NAME			09 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			10 STREET ADDRESS (P.O. Box, RFD #, etc.)			11 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			12 CITY			13 STATE			14 ZIP CODE		
01 NAME			02 D+B NUMBER			08 NAME			09 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			10 STREET ADDRESS (P.O. Box, RFD #, etc.)			11 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			12 CITY			13 STATE			14 ZIP CODE		
01 NAME			02 D+B NUMBER			08 NAME			09 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			10 STREET ADDRESS (P.O. Box, RFD #, etc.)			11 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			12 CITY			13 STATE			14 ZIP CODE		

III. PREVIOUS OWNER(S) (List most recent first)

IV. REALTY OWNER(S) (if applicable; list most recent first)

01 NAME see report table 2-2			02 D+B NUMBER			01 NAME N/A			02 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			05 CITY			06 STATE			07 ZIP CODE		
01 NAME			02 D+B NUMBER			01 NAME			02 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			05 CITY			06 STATE			07 ZIP CODE		
01 NAME			02 D+B NUMBER			01 NAME			02 D+B NUMBER								
03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE			03 STREET ADDRESS (P.O. Box, RFD #, etc.)			04 SIC CODE								
05 CITY			06 STATE			07 ZIP CODE			05 CITY			06 STATE			07 ZIP CODE		

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
1LD 180012585

II. CURRENT OPERATOR (Provide if different from owner)				OPERATOR'S PARENT COMPANY (If applicable)			
01 NAME Same as current owner		02 D+B NUMBER		10 NAME N/A		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER					
III. PREVIOUS OPERATOR(S) (List most recent first; provide only if different from owner)				PREVIOUS OPERATORS' PARENT COMPANIES (If applicable)			
01 NAME Same as previous owners		02 D+B NUMBER		10 NAME N/A		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					

IV. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

IEPA DLPC File # L1110355003



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
1LD 180012585

II. ON-SITE GENERATOR

01 NAME Same as owner	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE

III. OFF-SITE GENERATOR(S)

01 NAME N/A	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE

IV. TRANSPORTER(S)

01 NAME EWR	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY Coal City	06 STATE 07 ZIP CODE IL 60416	05 CITY	06 STATE 07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE 07 ZIP CODE	05 CITY	06 STATE 07 ZIP CODE

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

IEPA DLPC file # L1110355003





POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
140 180012585

II. PAST RESPONSE ACTIVITIES

01 ☐ A. WATER SUPPLY CLOSED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ B. TEMPORARY WATER SUPPLY PROVIDED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ C. PERMANENT WATER SUPPLY PROVIDED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ D. SPILLED MATERIAL REMOVED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ E. CONTAMINATED SOIL REMOVED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ F. WASTE REPACKAGED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ G. WASTE DISPOSED ELSEWHERE  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ H. ON SITE BURIAL  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ I. IN SITU CHEMICAL TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ J. IN SITU BIOLOGICAL TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ K. IN SITU PHYSICAL TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ L. ENCAPSULATION  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ M. EMERGENCY WASTE TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ N. CUTOFF WALLS  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ O. EMERGENCY DIKING/SURFACE WATER DIVERSION  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ P. CUTOFF TRENCHES/SUMP  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ Q. SUBSURFACE CUTOFF WALL  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
14D 180012585

II. PAST RESPONSE ACTIVITIES (Continued)

01 ☐ R. BARRIER WALLS CONSTRUCTED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ S. CAPPING/COVERING  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ T. BULK TANKAGE REPAIRED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ U. GROUT CURTAIN CONSTRUCTED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ V. BOTTOM SEALED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ W. GAS CONTROL  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ X. FIRE CONTROL  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ Y. LEACHATE TREATMENT  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ Z. AREA EVACUATED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ 1. ACCESS TO SITE RESTRICTED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ 2. POPULATION RELOCATED  
04 DESCRIPTION

02 DATE

03 AGENCY

01 ☐ 3. OTHER REMEDIAL ACTIVITIES  
04 DESCRIPTION

02 DATE

03 AGENCY

Adjacent village of Huntley property was cleaned-up  
(Soil removal) Near the village #4 well.

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

IEPA DLPC file # L1110355003



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 11 - ENFORCEMENT INFORMATION

I. IDENTIFICATION

01 STATE	02 SITE NUMBER
14D	180012585

II. ENFORCEMENT INFORMATION

01 PAST REGULATORY/ENFORCEMENT ACTION ☐ YES ☒ NO

02 DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

IEPA DLPC file # L1110355003

APPENDIX C  
TARGET COMPOUND LIST

# TARGET COMPOUND LIST

## Volatile Target Compounds

Compound	Water CRDL	Soil/Solid CRDL
1. chloromethane	10 ug/l	10 ug/kg
2. bromomethane	10	10
3. vinyl chloride	10	10
4. chloroethane	10	10
5. methylene chloride	5	5
6. acetone	10	10
7. carbon disulfide	5	5
8. 1,1-dichloroethene	5	5
9. 1,1-dichloroethane	5	5
10. t-1,2-dichloroethene	5	5
11. 1,2-dichloropropane	5	5
12. chloroform	5	5
13. 1,2-dichloroethane	5	5
14. 2-butanone	10	10
15. 1,1,1-trichloroethane	5	5
16. carbon tetrachloride	5	5
17. vinyl acetate	10	10
18. dichlorobromomethane	5	5
19. c-1,3-dichloropropene	5	5
20. trichloroethene	5	5
21. benzene	5	5
22. chlorodibromomethane	5	5
23. 1,1,2-trichloroethane	5	5
24. t-1,3-dichloropropene	5	5
25. 2-chloroethyl vinyl ether	10	10
26. bromoform	5	5
27. 2-hexanone	10	10
28. 4-methyl-2-pentanone	10	10
29. 1,1,2,2-tetrachloroethane	5	5
30. tetrachloroethene	5	5
31. toluene	5	5
32. chlorobenzene	5	5
33. ethylbenzene	5	5
34. styrene	5	5
35. total xylenes	15	15

CRDL - Contract Required Detection Limit

## Base/Neutral Target Compounds

Compound	Water CRDL	Soil/Solid CRDL
1. Hexachloroethane	10 ug/l	330 ug/kg
2. Bis (2-chloroethyl) ether	10	330
3. Benzyl Alcohol	10	330
4. Bis (2-chloroisopropyl) ether	10	330
5. N-nitrosodi-n-propylamine	10	330
6. Nitrobenzene	10	330
7. Hexachlorobutadiene	10	330
8. 2-Methylnaphthalene	10	330
9. 1,2,4-trichlorobenzene	10	330
10. Isophorone	10	330
11. Naphthalene	10	330
12. 4-Chloroaniline	10	330
13. Bis (2-chloroethoxy) methane	10	330
14. Hexachlorocyclopentadiene	10	330
15. 2-chloronaphthalene	10	330
16. 2-Nitroaniline	50	1600
17. Acenaphthylene	10	330
18. 3-Nitroaniline	50	1600
19. Acenaphthene	10	330
20. Dibenzofuran	10	330
21. Dimethylphthalate	10	330
22. 2,6-Dinitrotoluene	10	330
23. Fluorene	10	330
24. 4-Nitroaniline	50	1600
25. 4-Chlorophenyl-phenyl ether	10	330
26. 2,4-Dinitrotoluene	10	330
27. Diethylphthalate	10	330
28. N-Nitrosodiphenylamine	10	330
29. Hexachlorobenzene	10	330
30. Phenanthrene	10	330
31. 4-Bromophenyl-phenyl ether	10	330
32. Anthracene	10	330
33. Dibutylphthalate	10	330
34. Fluoranthene	10	330
35. Pyrene	10	330
36. Butyl benzyl phthalate	10	330
37. Bis (2-ethylhexyl) phthalate	10	330
38. Chrysene	10	330
39. Benzo (a) anthracene	10	330
40. 3,3'-Dichlorobenzidine	20	660
41. Di-n-octyl phthalate	10	330
42. Benzo (b) fluoranthene	10	330
43. Benzo (k) fluoranthene	10	330
44. Benzo (a) pyrene	10	330
45. Indeno (1,2,3-cd) pyrene	10	330
46. Dibenzo (a,h) anthracene	10	330
47. Benzo (g,h,i) perylene	10	330
48. 1,2-Dichlorobenzene	10	330
49. 1,3-Dichlorobenzene	10	330
50. 1,4-Dichlorobenzene	10	330

# Acid Target Compounds

Compound	Water CRDL	Soil/Solid CRDL
1. Benzoic Acid	50 ug/l	1600 ug/kg
2. Phenol	10	330
3. 2-chlorophenol	10	330
4. 2-nitrophenol	50	1600
5. 2-methylphenol	10	330
6. 2,4-dimethylphenol	10	330
7. 4-methylphenol	10	330
8. 2,4-dichlorophenol	10	330
9. 2,4,6-trichlorophenol	10	330
10. 2,4,5-trichlorophenol	50	1600
11. 4-chloro-3-methylphenol	10	330
12. 2,4-dinitrophenol	50	1600
13. 2-methyl-4,6-dinitrophenol	50	1600
14. Pentachlorophenol	50	1600
15. 4-nitrophenol	50	1600

# Pesticide Target Compounds

Compound	Water CRDL	Soil/Solid CRDL
1. alpha-BHC	.05 ug/l	8.0 ug/kg
2. beta-BHC	.05	8.0
3. delta-BHC	.05	8.0
4. Lindane (gamma-BHC)	.05	8.0
5. Heptachlor	.05	8.0
6. Aldrin	.05	8.0
7. Heptachlor epoxide	.05	8.0
8. Endosulfan I	.05	8.0
9. 4,4'-DDE	.10	16.0
10. Dieldrin	.10	16.0
11. Endrin	.10	16.0
12. 4,4'-DDD	.10	16.0
13. Endosulfan II	.10	16.0
14. 4,4'-DDT	.10	16.0
15. Endrin aldehyde	.10	16.0
16. Endosulfan sulfate	.10	16.0
17. Methoxychlor	.50	80.0
18. Chlordane	.50	80.0
19. Toxaphene	.50	80.0
20. Arochlor-1016	1.0	160.0
21. Arochlor-1221	.50	80.0
22. Arochlor-1232	.50	80.0
23. Arochlor-1242	.50	80.0
24. Arochlor-1248	.50	80.0
25. Arochlor-1254	1.0	160.0
26. Arochlor-1260	1.0	160.0



## Inorganic Target Compounds

### Metals Analyses (CRDL)-ug/l\*

Aluminum	200
Antimony	60
Arsenic	10
Barium	200
Beryllium	5
Cadmium	5
Chromium	10
Cobalt	50
Copper	25
Iron	100
Lead	5
Manganese	15
Mercury	0.2
Nickel	40
Selenium	5
Silver	10
Thallium	10
Vanadium	50
Zinc	20

### Other Inorganics

Cyanide  
 Sulfide  
~~Phenols~~  
~~Nitrogen Ammonia~~  
~~Nitrogen, Total Kjeldahl~~  
~~Nitrogen Nitrate~~  
~~Boron~~  
~~pH~~  
 Sulfate

\*Any analytical method specified in the Quality Assurance Project Plan (QAPP) may be utilized as long as the documented instrument or method detection limits meet the Contract Required Detection Level requirements. Higher detection levels may only be used in the following circumstance:

If the sample concentration exceeds two times the detection limit of the instrument or method in use, the value may be reported even though the instrument or method detection limit may not equal the CRDL. This is illustrated in the example below:

For lead:

Method in use -- ICP  
 Instrument Detection Limit (IDL) = 40  
 Sample Concentration = 85  
 Contract Required Detection Level (CRDL) = 5

The value of 85 may be reported even though instrument detection limit is greater than required detection level. The instrument or method detection limit must be documented as described in Form IIIX.

These CRDL are the instrument detection limits obtained in pure water that must be met using ICP/Flame AA or Furnace AA. The detection limits for samples may be considerably higher depending on the sample matrix.

**APPENDIX D**  
**SSI PHOTOGRAPHS**

# Photograph Location Map

April 25, 1990

Illinois Bell

Water  
Tower

Pump  
House

Well #4


Drum  
Storage

Fence

Metal  
Bldg.

CATTY CORPORATION

Chicago & North Western R.R.



DATE: 4-25-90

TIME: 6:00pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 19

LOCATION: Catty Corp.

11117 S. Church St.,

Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the Southwest of

Catty Corp.



DATE: 4-25-90

TIME: 6:00 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 20

LOCATION: Catty Corp.

11117 S. Church St.,

Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the south of Catty

corp. with Pres. Raymond

Scott on the left and

Purchasing Agent Gene

Konaszewski on the  
right





DATE: 4-25-90

TIME: 6:00 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 17

LOCATION: Catty Corp.

11117 S. Church St.,  
Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the northwest of the  
drum storage pad with  
Huntly Well #4 in the  
background



DATE: 4-25-90

TIME: 6:00 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 18

LOCATION: Catty Corp.

11117 S. Church St.,  
Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the west-southwest  
of the drum storage  
pad with the metal  
bldg. (warehouse) in  
the background





DATE: 4-25-90

TIME: 12:30 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 15

LOCATION: North of Pump  
house at Huntly Well  
#4, Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the southeast of X107  
sample location, 24'  
east and 3' North of  
the utility pole that's  
2' east of the Rd.



DATE: 4-25-90

TIME: 12:30 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 16

LOCATION: North of Pump  
house at Huntly Well  
#4, Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the south-southeast  
of X107 sample location





DATE: 4-25-90

TIME: 5:30 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 13

LOCATION: Catty Corp.

1117 S. Church St.,  
Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the northeast of X105  
sample location, 20'  
South of metal bldg. and  
6' east of fence



DATE: 4-25-90

TIME: 5:30pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 14

LOCATION: Catty Corp.

1117 S. Church St.,  
Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the Northwest of  
X105 sample location





DATE: 4-25-90

TIME: 4:15 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 11

LOCATION: Catty Corp.

11117 S. Church St.,

Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the east of X104

sample location on

the center of the

west side of the drum  
pad



DATE: 4-25-90

TIME: 4:15 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 12

LOCATION: Catty Corp.

11117 S. Church St.,

Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the east of X104

sample location





DATE: 4-25-90

TIME: 2:50pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 9

LOCATION: Catty Corp.

11117 S. Church St.,

Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the North-north west  
of X103 sample location,  
ON the center of the  
South side of the  
drum pad



DATE: 4-25-90

TIME: 2:50pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 10

LOCATION: Catty Corp.

11117 S. Church St.,

Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the Northwest of  
X103 sample location





DATE: 4-25-90

TIME: 3:30 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 7

LOCATION: Catty Corp.

11117 S. Church St.,

Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the west-southwest  
of X102 sample location,  
on the center of the  
east side of the drum  
pad



DATE: 4-25-90

TIME: 3:30 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 8

LOCATION: Catty Corp.

11117 S. Church St.,

Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the west-northwest  
of X102 sample location  
with Huntly Well #4  
in the background





DATE: 4-25-90

TIME: 1:00 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 1

LOCATION: Pump house

at Huntly Well #4

Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the east of Faucet  
used to collect G501



DATE: 4-25-90

TIME: 1:00 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 2

LOCATION: Pump house

at Huntly Well #4

Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the southeast of  
the Pump house with  
the drum storage  
area at Catty in the  
background.





DATE: 4-25-90

TIME: 1:50 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 3

LOCATION: Pump house

at Huntly Well #6

Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the southwest of

G502 sample location



DATE: 4-25-90

TIME: 1:50 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 4

LOCATION: Pump house

at Huntly Well #6

Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the North-Northwest

of G502 sample

location, east of Rt.

47 on Kreutzer Rd.





DATE: 4-25-90

TIME: 5:00 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 5

LOCATION: Catty Corp.

11117 S. Church St.,

Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the east-northeast of  
X101 sample location on  
the center of the north  
side of the drum pad



DATE: 4-25-90

TIME: 5:00 pm

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTO NUMBER: 6

LOCATION: Catty Corp.

11117 S. Church St.,

Huntly, IL McHenry Co.

COMMENTS: PICTURE TAKEN TOWARD

the west-southwest  
of X101 sample  
location



APPENDIX E

WELL LOGS



WELL	RAW SOURCE	STAT	RACK	LEGAL DESCRIPTION	QUAD	SCEPTLY	SETBACK	AQUIFER	DPH
			UP			BURL	SPRD		
1115100 - CRYSTAL MTS ASSN									
01 20169-WELL 1 SOUTH END OF KENT AVE	B	N		POPULATION: 110 SRVC CONN: 110 SRVC CONN: 36 FACL STATUS: A	027A	A2	400	5656	278
1115125 - OAKBROOK ESTS MHP									
01 20168-WELL 1	A	N		POPULATION: 138 SRVC CONN: 900M 027A A2	027A	A2	400	0101	150
1115150 - CRYSTAL CLEAR MTR CMPNY									
01 20145-W1 IN PMPHSE IN SE COR OF OLD DRIVE-IN	T	A		POPULATION: 900 SRVC CONN: 295 FACL STATUS: A	027A	A2	400	5661	512
02 20146-W2 N OF PMPHSE AT SE COR OF OLD DRIVE-IN	A	N		POPULATION: 625E 027A A2	027A	A2	400	0101	273
1115400 - KILLARNEY MTR CMPNY									
02 20157-WELL 2 AT 3111 KILLARNEY DR BY LAKEWOOD D	A	N		POPULATION: 1,176 SRVC CONN: 336 FACL STATUS: A	027A	A2	400	0101	250
1115730 - PRAIRIE RIDGE ASSN									
01 20162-W1 WHITE ASH RD N CRYL LK AV M SMITH RD	A	N		POPULATION: 100 SRVC CONN: 30 FACL STATUS: A	027A	A2	400	5661	360
1115760 - TURNBERRY UTL INC									
01 20158-W1 N TURNBRY TR E OF CLUBHOUSE DRIVE	A	N		POPULATION: 350 SRVC CONN: 100 FACL STATUS: A	027A	B1	200	5063	395
0895550 - POWERS MTR INC									
01 20087-POWERS ROAD ABOUT 1/2 MILE WEST OF HWY 47	A	N		POPULATION: 100 SRVC CONN: 27 FACL STATUS: A	027B	C2	400	0101	80
1118030 - HUNLEY									
01 20203-WELL 4 E HWY 47 BETWEEN HUNTLEY RD & RR	A	N		POPULATION: 1,650 SRVC CONN: 600 FACL STATUS: A	027B	C2	400	0101	63
02 20204-WELL 5 AT NEW ELEVATED YAK	A	N		POPULATION: 43M 07E 28 6F 18655 1535E 027B C2	027B	C2	400	0101	93
03 20205-WELL 6 N SIDE KREUTZER RD E OF RT 47	A	N		POPULATION: 43M 07E 33 7A 75N 800E 027B C2	027B	C2	400	0101	154
0890200 - CARPENTERSVILLE									
01 20028-WELL 3 JCT LK MARION & ALCONQUIN RD	I	N		POPULATION: 23,270 SRVC CONN: 5,500 FACL STATUS: A	027D	A2	400	0101	72
02 20029-WELL 5 NE CORNER AUSTIN E SACRAMENTO DR	A	N		POPULATION: 400M 027D A2	027D	A2	400	0101	69
03 20030-WELL 6 300 FT E OF TRIMPT PLT	A	N		POPULATION: 900M 027D A2	027D	A2	400	0101	128
0890250 - EAST DUNDEE									
01 20032-SPRING-BARRINGTON AVE	A	N		POPULATION: 2,650 SRVC CONN: 830 FACL STATUS: A	027D	A2	400	0101	187
02 20033-WELL 2 408 BARRINGTON AVE	A	N		POPULATION: 400M 027D A2	027D	A2	400	0101	69
03 20034-WELL 3 TOP OF BARRINGTON AVE HILL	A	N		POPULATION: 1250E 027D A2	027D	A2	400	0101	128
0890400 - GILBERTS									
01 20051-DUNHILL SUBD EAST TYRRELL ROAD N I90	A	N		POPULATION: 320 SRVC CONN: 91 FACL STATUS: A	027D	C2	400	5656	187
0890750 - SLEEPY HOLLOW									
20094-WEST END OF WILLOW LANE	I	N		POPULATION: 2,300 SRVC CONN: 625 FACL STATUS: A	027D	AX	400	0101	34
20095-WEST END OF WILLOW LANE	I	N		POPULATION: 1450E 027D AX	027D	AX	400	0101	46
0890800 - SOUTH ELGIN									
03 20098-WELL 5 E OF HWY 31 ON ROSS AVE	A	N		POPULATION: 6,400 SRVC CONN: 2,280 FACL STATUS: A	027D	A2	400	0101	68
0890950 - WEST DUNDEE									
01 20113-WELL 1 DUNNING AVE AT SECOND STREET	I	N		POPULATION: 3,750 SRVC CONN: 1,070 FACL STATUS: A	027D	AX	400	6693	123
02 20114-W2 BY 1MG EL TK IN TOWER PK 4TH & MAIN	I	N		POPULATION: 200M 027D AX	027D	A2	400	0101	87

The pumping equipment presently installed is a 13-stage Deming turbine pump (Serial No. MT5673) set at 63 ft, rated at 80 gpm, and powered by a 5-hp 3600 rpm U.S. electric motor (Serial No. 2421639).

A mineral analysis made by the Illinois Environmental Protection Agency (Lab. No. B0018164) of a sample collected May 10, 1972, after pumping for 30 min, showed the water to have a hardness of 312 mg/l, total dissolved minerals of 400 mg/l, and an iron content of 1.05 mg/l.

WELL NO. 2, finished in sand and gravel, was completed in July 1958 to a depth of 108 ft by the Henry Boysen Co., Libertyville. The well is located 12 ft south of Well No. 1, approximately 1712 ft S and 1500 ft W of the NE corner of Section 18, T44N, R9E. The land surface elevation at the well is approximately 750 ft.

A drillers log of Well No. 2 follows:

Strata	Thickness (ft)	Depth (ft)
Top soil	6	6
Gravel	34	40
Sand with clay	50	90
Gravel	8	98
Sand and gravel	10	108

A 12-in. diameter hole was drilled to a depth of 108 ft. The well is cased with 10-in. pipe from 2 ft above the pump-

house floor to a depth of 93 ft followed by 15 ft of 6-in. No. 14 slot Cook screen.

The pumping equipment presently installed is an 8-in., 10-stage Byron Jackson turbine pump (Type OKH, Serial No. 357006) set at 87 ft, rated at 275 gpm at about 195 ft TDH, and powered by a 20-hp 1760 rpm U.S. electric motor.

The following mineral analysis made by the Illinois Environmental Protection Agency (Lab. No. 02688) is for a water sample from the well collected November 9, 1971, after 30 min of pumping at 230 gpm.

#### WELL NO. 2, LABORATORY NO. 02688

	mg/l	me/l		mg/l	me/l
Iron	Fe	0.7	Silica	SiO <sub>2</sub>	23
Manganese	Mn	0.0	Fluoride	F	0.3
Ammonium	NH <sub>4</sub>	0.3	Boron	B	0.0
Sodium	Na	5.2	Nitrate	NO <sub>3</sub>	0
Potassium	K	0.9	Chloride	Cl	9.0
Calcium	Ca	84.8	Sulfate	SO <sub>4</sub>	28
Magnesium	Mg	44	Alkalinity (as CaCO <sub>3</sub> )		340
			Hardness (as CaCO <sub>3</sub> )		392
Barium	Ba	0.3	Total dissolved minerals		443
Copper	Cu	0.0	pH (as rec'd)		7.4
Cadmium	Cd	0.00	Radioactivity		
Chromium	Cr	0.0	Alpha pc/l		0
Lead	Pb	0.00	± deviation		1
Mercury	Hg	< 0.0005	Beta pc/l		3
Nickel	Ni	0.0	± deviation		2
Silver	Ag	0.0			
Zinc	Zn	0.0			

## HUNTLEY

The village of Huntley (1432) installed a public water supply in 1903. One well (No. 5) is in use and two other wells (Nos. 3 and 4) are available for emergency use. In 1950 there were 200 services, 180 were metered; the average and maximum daily pumpages were 40,000 and 80,000 gpd, respectively. In 1975 there were 600 services, all metered; the average and maximum daily pumpages were 301,938 and 500,000 gpd, respectively. The water from Well No. 5 is chlorinated, fluoridated, and treated with polyphosphate to keep iron in solution.

WELL NO. 1, finished in sand and gravel, was completed to a depth of 74.2 ft. This well was abandoned and capped in 1947. The well was located south of Main St. and west of Railroad St., approximately 306 ft S and 1800 ft E of the NW corner of Section 33, T43N, R7E. The land surface elevation at the well is approximately 889 ft.

The well was cased with 6-in. pipe to an unknown depth. In 1921 this well was cleaned and a new screen was installed.

WELL NO. 2, finished in sand and gravel, was completed to a depth of 74 ft. This well was abandoned and capped in 1954. The well was located about 6 ft north of Well No. 1, approximately 300 ft S and 1800 ft E of the NW corner of Section 33, T43N, R7E. The land surface elevation at the well is approximately 889 ft.

The well was cased with 6-in. steel pipe from above the floor of a 6-ft deep pit to a depth of 64 ft followed by 10 ft of screen. In 1921 the well was cleaned and a new screen was installed and in 1935 the screen was cleaned and reinstalled.

WELL NO. 3, finished in sand and gravel, was originally constructed to a depth of 69 ft, and then the well was deepened in May 1947 to a depth of 74 ft by W. R. Boetsch & Son, Crystal Lake. This well is available for emergency use. The well is located at the foot of the elevated tank just south of the business district, approximately 290 ft S and 1775 ft E of the NW corner of Section 33, T43N, R7E. The land surface elevation at the well is approximately 890 ft.

A 10-in. diameter hole was drilled to a depth of 74 ft. The well is cased with 10-in. ID pipe from 0.9 ft above the pumphouse floor to a depth of 54 ft followed by 20 ft of screen. In 1921 the well was cleaned and a new screen was installed and in 1935 the screen was cleaned and reinstalled.

In May 1947, W. R. Boetsch & Son, Crystal Lake, pulled the sand screen, cleaned and deepened the well about 5 ft, and reinserted a screen.

On July 17, 1947, the well reportedly produced 100 gpm for 6 hr with a drawdown of 3.0 ft from a nonpumping water



level of 23.3 ft below land surface.

The pumping equipment presently installed consists of a 5-hp 1800 rpm U.S. electric motor (Serial No. 2679408), a 6-in., 11-stage Aurora turbine pump (No. 11687) set at 50 ft, rated at 100 gpm at about 140 ft TDH, and has 50 ft of 4-in. column pipe. The well is equipped with 50 ft of airline.

A mineral analysis of a sample (Lab. No. 111119) collected July 17, 1947, after pumping for 6 hr at 100 gpm, showed the water to have a hardness of 395 mg/l, total dissolved minerals of 447 mg/l, and an iron content of 1.3 mg/l.

Prior to the construction of Well No. 4, a test well (No. 1-53), finished in sand and gravel, was completed in November 1953 to a depth of 76 ft by the Layne-Western Co., Aurora. The test well was located under the elevated tank on Woodstock St., approximately 250 ft S and 1800 ft E of the NW corner of Section 33, T43N, R7E.

A sample study summary log of Test Well No. 1-53 furnished by the State Geological Survey follows:

Strata	Thickness (ft)	Depth (ft)
PLEISTOCENE SERIES		
Soil, brown	5	5
Till, very gravelly, sandy	20	25
Sand, very gravelly, medium to very coarse	10	35
Gravel, very sandy, granular	27.5	62.5
Sand, very gravelly, medium to very coarse	2.5	65
Sand, silty, very fine to coarse	5	70
Sand, gravelly, medium to very coarse	6	76

WELL NO. 4, finished in sand and gravel, was completed in November 1953 to a depth of 63 ft (measured in 1974 at 61 ft deep) by the Layne-Western Co., Aurora. This well is available for emergency use. The well is located under the elevated tank 50 ft west of the test well, approximately 250 ft S and 1750 ft E of the NW corner of Section 33, T43N, R7E. The land surface elevation at the well is approximately 889 ft.

A drillers log of Well No. 4 follows:

Strata	Thickness (ft)	Depth (ft)
Till	1	1
Natural and black fill	2	3
Blue clay and boulders	37	40
Coarse gravel and boulders	23	63

A 34-in. diameter hole was drilled to a depth of 63 ft. The well is cased with 12-in. pipe from 1.7 ft above the pump-house floor to a depth of 53 ft followed by 10 ft of 12-in. No. 8 (0.030 in.) Layne bronze shutter screen. The annulus between the bore hole and casing-screen assembly is filled with clay fill from 0 to 28 ft and with 11.5 yards of pea gravel and coarse sand from 28 to 63 ft.

A production test was conducted on November 11-12, 1953, by representatives of the driller, the State Water Survey, and Baxter and Woodman, Consulting Engineers. After 24 hr of pumping at rates of 219 to 323 gpm, the final draw-

down was 10.0 ft from a nonpumping water level of 21.0 ft below land surface. Forty-two min after pumping was stopped, the water level had recovered to 25.8 ft. Well No. 2 was pumping during the first part of the test.

In September 1975, the nonpumping water level was reported to be 22 ft.

The pumping equipment presently installed consists of a 20-hp General Electric motor, an 8-in., 7-stage Johnston turbine pump set at 40 ft, rated at 250 gpm at about 200 ft TDH, and has 40 ft of 6-in. column pipe. A 5-ft section of 6-in. suction pipe is attached to the pump intake. The well is equipped with 40 ft of airline.

A partial analysis of a sample (Lab. No. 148164) collected November 7, 1958, after pumping for 5 min, showed the water to have a hardness of 440 mg/l, total dissolved minerals of 437 mg/l, and an iron content of 1.4 mg/l.

WELL NO. 5, finished in sand and gravel, was completed in October 1969 to a depth of 95 ft by the J. P. Miller Artesian Well Co., Brookfield. The well is located by the new elevated tank north of the village on the east side of Route 47, approximately 1865 ft S and 1535 ft E of the NW corner of Section 28, T43N, R7E. The land surface elevation at the well is approximately 900 ft.

A drillers log of Well No. 5 follows:

Strata	Thickness (ft)	Depth (ft)
Clay	20	20
Gravel	5	25
Blue clay	50	75
Sand and gravel	20	95

A 36-in. diameter hole was drilled to a depth of 95 ft. The well is cased with 12-in. pipe from land surface to a depth of 80 ft followed by 15 ft of 12-in. No. 50 slot Johnson stainless steel screen. The annulus between the bore hole and casing-screen assembly is filled with cement grout from 0 to 20 ft, with impervious fill from 20 to 50 ft, and with No. 2 Northern gravel from 50 to 95 ft.

Upon completion, the well reportedly produced 600 gpm for 24 hr with a drawdown of 30 ft from a nonpumping water level of 29 ft below land surface.

In January 1973, this well was treated with 1000 gal of acid by the Layne-Western Co., Aurora. After acidizing, the well reportedly produced 488 gpm with a drawdown of 41 ft from a nonpumping water level of 27 ft.

The pumping equipment presently installed consists of a 40-hp 1800 rpm U.S. Holloshaft electric motor (Serial No. RR-800-00-170-CR2023853), a 10-in., 4-stage Layne vertical turbine pump (Serial No. 62834) set at 70 ft, rated at 600 gpm at about 200 ft TDH, and has 70 ft of 8-in. column pipe. The well is equipped with 70 ft of airline.

The following mineral analysis made by the Illinois Environmental Protection Agency (Lab. No. B18268) is for a water sample from the well collected October 21, 1975, after 3.5 hr of pumping at 400 gpm.

# WELL NO. 5, LABORATORY NO. B18268

		mg/l	me/l			mg/l	me/l
Iron	Fe	0.4		Silica	SiO <sub>2</sub>	17	
Manganese	Mn	0.13		Fluoride	F	0.3	0.02
Ammonium	NH <sub>4</sub>	0.1	0.01	Boron	B	0.1	
Sodium	Na	11	0.48	Nitrate	NO <sub>3</sub>	0.8	0.01
Potassium	K	1.8	0.05	Chloride	Cl	20	0.56
Calcium	Ca	100	4.99	Sulfate	SO <sub>4</sub>	83	1.73
Magnesium	Mg	54	4.44	Alkalinity (as CaCO <sub>3</sub> )		386	7.72
Arsenic	As	0.00		Hardness (as CaCO <sub>3</sub> )		471	9.42
Barium	Ba	0.1					
Copper	Cu	0.00					
Cadmium	Cd	0.00		Total dissolved minerals		532	
Chromium	Cr	0.00					
Lead	Pb	0.00					
Mercury	Hg	0.0000		pH (as rec'd)		8.3	
Nickel	Ni	0.0		Radioactivity			
Selenium	Se	0.00		Alpha pc/l		1.6	
Silver	Ag	0.00		± deviation		1.7	
Cyanide	CN	0.01		Beta pc/l		4.2	
Zinc	Zn	0.0		± deviation		2.0	

## ISLAND LAKE

The village of Island Lake (1973) installed a public water supply in 1940. This village also extends into Lake County and two of the wells are located there. The water system is owned and operated by the Island Lake Water Co. Three wells (Nos. 1, 2, and 3) are in use. In 1952 there were 450 services, 350 were metered. In 1973 there were 580 services, all metered; the average and maximum daily pump-ages were 47,022 and 70,000 gpd, respectively. The water is chlorinated and fluoridated.

WELL NO. 1 (Well 19-U), finished in sand and gravel, was completed in July 1940 to a depth of 116 ft (effective depth 115 ft) by Henry Boysen, Jr., Libertyville. The well is located at the corner of Midway and Fairfield Drives, approximately 1130 ft N and 190 ft E of the SW corner of Section 21, T44N, R9E, Lake County. The land surface elevation at the well is approximately 770 ft.

A drillers log of Well No. 1 follows:

Strata	Thickness (ft)	Depth (ft)
Yellow stoney gravel	40	40
Dirty gravel and sand	51	91
Gravel and sand	25	116

A 10-in. diameter hole was drilled to a depth of 116 ft. The well is cased with 10-in. wrought iron pipe from 1.2 ft above the floor of a 12-ft deep pit to a depth of 92 ft followed by 24 ft of 9.6-in. Cook screen. The screened section from top to bottom consists of 5 ft of No. 60 slot, 10 ft of No. 14 slot, and 8 ft of No. 40 slot with 1 ft of blank section at the bottom.

Upon completion, the well reportedly produced 503 gpm for 8 hr with a drawdown of 11 ft from a nonpumping water level of 29 ft below land surface.

On October 27, 1959, the nonpumping water level was reported to be 26 ft below land surface.

The well was acidized in 1960 by the Dow Chemical Co. and the yield was reportedly improved from 115 to 435 gpm.

On May 20, 1963, the nonpumping water level was reported to be 30 ft.

The pumping equipment presently installed consists of a 20-hp 1800 rpm U.S. electric motor, an 8-in., 11-stage Aurora turbine pump (No. 69213) set at 90 ft, rated at 200 gpm at about 250 ft TDH, and has 90 ft of 5-in. column pipe. The well is equipped with 90 ft of airline.

A mineral analysis made by the Illinois Environmental Protection Agency (Lab. No. C004680) of a sample collected December 18, 1973, after pumping for 30 min at 300 gpm, showed the water to have a hardness of 397 mg/l, total dissolved minerals of 466 mg/l, and an iron content of 1.4 mg/l.

WELL NO. 2 (Well K-9), finished in sand and gravel, was completed in June 1945 to a depth of 95 ft (reported in March 1960 at 92 ft deep) by Henry Boysen, Jr., Libertyville. The well is located at the corner of Eastway and Forest Drives, approximately 1385 ft S and 1255 ft E of the NW corner of Section 21, T44N, R9E, Lake County. The land surface elevation at the well is approximately 770 ft.

A drillers log of Well No. 2 follows:

Strata	Thickness (ft)	Depth (ft)
Gravel	36	36
Sand	48	84
Gravel	11	95

An 8-in. diameter hole was drilled to a depth of 95 ft. The well is cased with 8-in. steel pipe from 1 ft above land surface to a depth of 84 ft followed by 11 ft (10 ft slotted) of 8-in. No. 14 slot Cook red brass screen.

Upon completion, after pumping for 2 days, the well reportedly produced 280 gpm with a drawdown of 16 ft from

# WATER WELL SEALING FORM

Illinois Department of Public Health  
525 West Jefferson Street  
Springfield, Illinois 62761

This form shall be submitted to this Department not more than 30 days after a potable water well, boring or monitoring well is sealed. Such wells are to be sealed not more than 30 days after they are abandoned in accordance with the sealing requirements in the Water Well Construction Code.

1. Ownership (Name of Controlling Party) Catty Corporation  
2. Well Location: Church & Mill Streets  
Huntley McHenry  
City County

General Description: Section 33 Township 43 N  
Range 7 E

3. Year Drilled Unknown  
4. Drilling Permit No. (and date, if known) Unknown  
5. Type of Well: Bored \_\_\_\_\_ Drilled X Other \_\_\_\_\_  
6. Total Depth 67 ft 6 in Diameter (inches) 19"  
7. Formation clear of obstruction X yes \_\_\_\_\_ no \_\_\_\_\_  
If no, depth - location of obstruction \_\_\_\_\_

8. DETAILS OF PLUGGING:  
Filled with 3/8" & under aggregate washed stone From 67'6" To 50'7" feet  
Kind of plug 2 1/4 yds cement From 50'7" To 0 feet  
Mixture of:  
Filled with 564 lbs Portland Cement To \_\_\_\_\_ feet  
2000 lbs Sand From \_\_\_\_\_ To \_\_\_\_\_ feet  
10 lbs Plasticizer by Malon (Super) From \_\_\_\_\_ To \_\_\_\_\_ feet  
36 lbs Bentonite From \_\_\_\_\_ To \_\_\_\_\_ feet  
Kind of plug per yard From \_\_\_\_\_ To \_\_\_\_\_ feet

9. CASING RECORD  
Over 3 feet of casing removed \_\_\_\_\_ Yes \_\_\_\_\_ No X  
If well casing consists of brick, stone, concrete blocks, porous tile, or other porous material, casing was removed to a depth of 10 feet below the surface. Yes \_\_\_\_\_ No \_\_\_\_\_

10. Date Well was Sealed June 23 1988

11. Licensed water well driller or other person approved by the Department performing well sealing  
Marvin R. Nice  
11762 U.S. Rt. 20 Garden Prairie, Ill 61038  
102 002458

RECEIVED  
JUL 01 1988  
DIVISION OF  
ENVIRONMENTAL HEALTH

11/87

IL 482-0631

Important Notice:  
This State Agency is requesting disclosure of information that is necessary to accomplish the statutory purpose as outlined under Public Act 83-2813. Disclosure of this information is mandatory. This form has been approved by the Forms Management Center.

Batty H.D. Corp location - T43N, R7E Section 33. NW 1/4

McHenry Co., Kane Co.

	T43N R7E	T43N R6E	<sup>Kane Co.</sup> T42N R7E
1 mile radius Sections:	27-29, 32-34		4
2 mile radius Sections	20-22, 26, 30, 33		3, 5
3 mile radius Sections	14-19, 23-25, 36	24, 25, 36	7-11

Kane Co. T42N R6W: 1

8

T43N R8W: 24, 25, 36

Kane Co. T42N R8W: 1

Total Sections) T43N R7E: 14-36

T43N R6E: 24, 25, 36

T43N R8E: 24, 25, 36

T42N R7E: 3-5, 7-11

T42N R6E: 1

T42N R8E: 1

**FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEY'S SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.**

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

- 1 Type of Well
- a. Dug\_\_\_\_. Bored\_\_\_\_. Hole Diam. 6 in. Depth 260 ft.  
Curb material\_\_\_\_. Burled Slab: Yes\_\_\_\_ No\_\_\_\_  
b. Driven\_\_\_\_. Drive Pipe Diam.\_\_\_\_ in. Depth\_\_\_\_ ft.  
c. Drilled x. Finished in Drift\_\_\_\_. In Rock\_\_\_\_.  
Tubular\_\_\_\_. Gravel Packed\_\_\_\_.  
d. Grout: \_\_\_\_\_

(KIND)	FROM (P.)	TO (P.)

2. Distance to Nearest:  
Building \_\_\_\_\_ Ft.      Sepage Tile Field \_\_\_\_\_  
Cess Pool \_\_\_\_\_      Sewer (non Cast Iron) \_\_\_\_\_  
Privy \_\_\_\_\_      Sewer (Cast Iron) \_\_\_\_\_  
Septic Tank \_\_\_\_\_      Barnyard \_\_\_\_\_  
Leaching Pit \_\_\_\_\_      Manure Pile \_\_\_\_\_
3. Well furnishes water for human consumption? Yes \_\_\_\_\_ No \_\_\_\_\_
4. Date well completed 8/18/80
5. Permanent Pump Installed? Yes X Date 10/23/80 No \_\_\_\_\_  
Manufacturer Aermotor Type sub Location \_\_\_\_\_  
Capacity 50 \_\_\_\_\_ gal. Depth of Setting 84 \_\_\_\_\_ Ft.
6. Well Top Sealed? Yes X No \_\_\_\_\_ Type \_\_\_\_\_
7. Pitless Adapter Installed? Yes X No \_\_\_\_\_  
Manufacturer BAKER Model Number snappy  
How attached to casing? compression
8. Well Disinfected? Yes X No \_\_\_\_\_
9. Pump and Equipment Disinfected? Yes X No \_\_\_\_\_
10. Pressure Tank Size 86 \_\_\_\_\_ gal. Type captive air (2 tank  
Location \_\_\_\_\_
11. Water Sample Submitted? Yes \_\_\_\_\_ No X

REMARKS:

10. Property owner Matt Tures Sons Well No. \_\_\_\_\_  
Address 9810 Dundee Road, Huntley, IL 60142  
Driller William M. Boetsch License No. 92-436  
Permit No. 94441 Date 6/18/80  
11. Water from Limestone 13. County McHenry  
Formation  
at depth 230 to 260 ft.  
14. Screen: Diam. \_\_\_\_\_ in.  
Length: \_\_\_\_\_ ft. Slot \_\_\_\_\_  
Elev. \_\_\_\_\_

Diam. (in.)	Kind and Weight	From (ft.)	To (ft.)
6	pvc	1	215
6	black steel	215	240

16. Size Hole below casing: 6 in. *Long + Commercial*  
 17. Static level 60 ft. below casing top which is 1 ft. above ground level. Pumping level 120 ft. when pumping at 60 gpm for 2 hours.

18.	FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
	blakk loam	4	4
	yellow clay	6	10
	sand, gravel	25	35
	layered red clay, fine sand	60	95
	gravel, sand	3	98
	red clay, sand	82	180
	very hard blue-green shale, layered limestone	50	230
	gray limestone	30	260

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Wm. D. Eastick DATE 11/20/80

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

White Copy - Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

### 1. Type of Well

- a. Dug          Bored          Hole Diam. 24 in. Depth 85 ft.  
Curb material          Burled Slab: Yes          No
- b. Driven          Drive Pipe Diam. 12 in. Depth 65 ft.
- c. Drilled X Finished in Drift X In Rock           
Tubular          Gravel Packed 1/8 x 1/8 pea gravel

### d. Grout:

(KIND)	FROM (FT.)	TO (FT.)
slurry	0	20

### 2. Distance to Nearest:

- Building          Ft. Seepage Tile Field           
Cess Pool          Sewer (non Cast iron)           
Privy          Sewer (Cast iron)           
Septic Tank          Barnyard           
Leaching Pit          Manure Pile

3. Well furnishes water for human consumption? Yes X No           
4. Date well completed 6/14/79

5. Permanent Pump Installed? Yes X Date 2/4/80 No           
Manufacturer Sta-Rite Type sub Location           
Capacity 350 gpm. Depth of Setting 50 Ft.

6. Well Top Sealed? Yes X No          Type

7. Pitless Adapter Installed? Yes X No          Model Number 6PS1214NBWE04M  
Manufacturer Baker How attached to casing? welded

8. Well Disinfected? Yes X No

9. Pump and Equipment Disinfected? Yes X No

10. Pressure Tank Size 25000 gal. Type ground storage  
Location

11. Water Sample Submitted? Yes X No

- REMARKS:

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner Wabash Tape Corp. Well No.           
Address 221 E. Main Street, Huntley, IL 60142  
Driller William M. Boetsch License No. 92-436  
11. Permit No. 85993 Date 5/25/79  
12. Water from gravel 13. County McHenry

- at depth 60 to 85 ft. Sec. 3319  
14. Screen: Diam. 12 in. Twp. 43N  
Length: 20 ft. Slot 100 Rge. 7E  
Elev.

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)	SHOW LOCATION IN SECTION PLAT 200' N 100' W 5E/4 NE NE industrial
12	black steel	1	65	

15. Casing and Liner Pipe

16. Size Hole below casing: 0 in.  
17. Static level 19 ft. below casing top which is 1 ft. above ground level. Pumping level 47 ft. when pumping at 450 gpm for 2 hours.

FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
top soil	1	1
sand, gravel	9	10
blue clay	15	25
peet	5	30
pink clay	30	60
gravel	25	85

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED          DATE 2/6/80

FILL IN ALL PERTINENT INFORMATION REQUESTED MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, ROOM 615, STATE OFFICE BUILDING, SPRINGFIELD, ILLINOIS 62706. DO NOT DETACH GEOLOGICAL / WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

# ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

## 1. Type of Well

- a. Dug ☐ Bored ☐ Hole Diam. 10 in. Depth 10 ft.  
Curb material concrete Buried Slab: Yes ☐ No ☐
- b. Driven ☐ Drive Pipe Diam. 10 in. Depth 10 ft.
- c. Drilled ☒ Finished in Drift ☒ In Rock ☐  
Tubular ☐ Gravel Packed ☐
- d. Grout: ☐

(KIND)	FROM (FT.)	TO (FT.)

## 2. Distance to Nearest:

- Building 10 Ft. Seepage Tile Field 10
- Cess Pool 10 Sewer (non Cast iron) 10
- Privy 10 Sewer (Cast iron) 10
- Septic Tank 10 Barnyard 10
- Leaching Pit 10 Manure Pile 10

## 3. Is water from this well to be used for human consumption?

Yes ☒ No ☐4. Date well completed March 7, 19685. Permanent Pump Installed? Yes ☒ No ☐Manufacturer Red Oak City Type submersibleCapacity 10 gpm. Depth of setting 10 ft.6. Well Top Sealed? Yes ☒ No ☐Pitless Adaptor Installed? Yes ☒ No ☐Well Disinfected? Yes ☒ No ☐7. Water Sample Submitted? Yes ☒ No ☐

## REMARKS:

MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, ROOM 615, STATE OFFICE BUILDING, SPRINGFIELD, ILLINOIS 62706. DO NOT DETACH GEOLOGICAL / WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

## Geological and Water Surveys Well Record

10. Property owner Harold K. Kende Well No. 10Address 1000 N. 10th St.Driller Harold K. Kende License No. 1011. Permit No. 10 Date 10/10/6812. Water from sand & gravel 13. County 10at depth 48 to 51 ft.14. Screen: Diam. 10 in.Length: 10 ft. Slot 10Elev. 10

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
<u>3</u>	<u>15 lb. per ft.</u>	<u>0</u>	<u>51</u>
	<u>spring steel</u>		

SHOW LOCATION IN SECTION PLAT

446' N 761'ESW 1/4 NE16. Size Hole below casing: 5 in.17. Static level 14 ft. below casing top which is 14above ground level. Pumping level 14 ft. when pumping at 24gpm for 1 hours.

18. FORMATIONS PASSED THROUGH

THICKNESS

DEPTH OF BOTTOM

0 to 20 ft. yellow clay20-48 pink clay48-51 sand & gravel

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Charles C. Kende DATE March 19, 1970

# INSTRUCTIONS TO DRILL

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

White Copy -  
Ill. Dept. of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

- Type of Well
  - Dug ☐ Bored ☐ Hole Diam. 5 in. Depth 215 ft.
  - Curb material ☐ Buried Slab: Yes ☐ No ☐
  - Driven ☐ Drive Pipe Diam. ☐ in. Depth ☐ ft.
  - Drilled ☒ Finished in Drift ☐ In Rock ☒
  - Tubular ☐ Gravel Packed ☐
  - Grout:
 

(KIND)	FROM (Ft.)	TO (Ft.)
Cuttings	0	204
- Distance to Nearest:
 

Building	<u>40</u> Ft.	Seepage Tile Field	
Cess Pool		Sewer (non Cast iron)	
Privy		Sewer (Cast iron)	
Septic Tank	<u>68</u>	Barnyard	
Leaching Pit		Manure Pile	
- Well furnishes water for human consumption? Yes ☒ No ☐
- Date well completed 3/16/88
- Permanent Pump Installed? Yes ☒ Date 3/29/88 No ☐

Manufacturer	<u>Delta</u>	Type Subm.	<u>Location in well</u>
Capacity	<u>10</u> gpm.	Depth of Setting	<u>60</u> Ft.
- Well Top Sealed? Yes ☒ No ☐ Type Williams Cap
- Pitless Adapter Installed? Yes ☒ No ☐

Manufacturer	<u>Williams</u>	Model Number	<u>R50AC</u>
--------------	-----------------	--------------	--------------
- How attached to casing? Locknut
- Well Disinfected? Yes ☒ No ☐
- Pump and Equipment Disinfected? Yes ☒ No ☐
- Pressure Tank Size 80 gal. Type Captive Air
- Location Garage
- Water Sample Submitted? Yes ☐ No ☒

1433  
CP

Owner instructed to take sample.

### REMARKS:

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

- Property owner Terry Todd Well No. Elgin, Ill  
Address 494 Lincoln Avenue  
Driller Marvin R. Nice License No. 102 002458
- Permit No. 136004 Date 10/2/87
- Water from Limestone 13. County McHenry
- at depth 204 to 215 ft. Sec. 33.4e  
Screen: Diam. 5 in. Twp. 43N  
Length: 15 ft. Slot Rge. 7E  
Elev. 75


Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
5"	Black Steel	0	204
	15 lbs per ft		

SHOW LOCATION IN SECTION PLAT  
SW SW NE

- Size Hole below casing: 5 in.
- Static level 30 ft. below casing top which is 1 ft. above ground level. Pumping level 40 ft. when pumping at 10 gpm for 4 hours.

FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Top Soil	2	2
Yellow Clay & Sand	18	20
Sand	20	40
Gravel	20	60
Clay	144	204
Limestone	11	215

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Therese DATE 5/25/88



# ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

1. Type of Well
  - a. Dug ☐ Bored ☒ Hole Diam. 5 in. Depth 40 ft.
  - Curb material ☐ Buried Slab: Yes ☐ No ☐
  - b. Driven ☐ Drive Pipe Diam. ☐ in. Depth ☐ ft.
  - c. Drilled ☒ Finished in Drift ☒ In Rock ☐
  - Tubular ☐ Gravel Packed ☐
  - d. Grout: ☐

(KIND)	FROM (FT.)	TO (FT.)

2. Distance to Nearest:
  - Building 3 Ft. Seepage Tile Field 80
  - Cess Pool 75 Sewer (non Cast Iron) ☐
  - Privy ☐ Sewer (Cast Iron) ☐
  - Septic Tank 75 Barnyard ☐
  - Leaching Pit ☐ Manure Pile ☐

3. Is water from this well to be used for human consumption?
  - Yes ☒ No ☐

4. Date well completed Oct 15 1967
5. Permanent Pump Installed? Yes ☒ No ☐
  - Manufacturer Red Jacket Type Submersible
  - Capacity 8 gpm. Depth of setting 30 ft.
6. Well Top Sealed? Yes ☒ No ☐
7. Pitless Adaptor Installed? Yes ☒ No ☐
8. Well Disinfected? Yes ☒ No ☐
9. Water Sample Submitted? Yes ☐ No ☐

DIVISION OF SANITARY ENGINEERING  
ILLINOIS DEPT. OF PUBLIC HEALTH

REMARKS:

# GEOLOGICAL WATER SURVEYS WATER WELL RECORD

10. Dept. Mines and Minerals permit No. AF5084 Year 1969
11. Property owner John Cole, Jr. Well No.
- Address 1401 E. Main St. Quincy, Ill.
- Driller Charles Sigrist License No. 92-135
12. Water from Bedrock 13. County McHenry
- at depth   to   ft. Sec. 33.7c
14. Screen: Diam.   in. Twp. 43N
- Length:   ft. Slot   Rag. 7F Elev.

## 15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (ft.)	To (ft.)
<u>5</u>	<u>5" PVC</u>		
	<u>15 lb. per ft.</u>		

SHOW LOCATION IN SECTION PLAT	
<u>137°N 45°W</u>	<u>N56°NWN</u>

16. Size Hole below casing: 5 in.
17. Static level 30 ft. below casing top which is 13 ft. above ground level. Pumping level: 30 ft. when pumping at 16 gpm for 1 hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>0 To 20 ft. dry sand and gravel</u>		
<u>20 To 38 ft. gray sandy clay</u>		
<u>VED To 40 ft. black coarse sand</u>		

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Charles Sigrist DATE Nov 4 1968  
Charles Sigrist

RECEIVED

NOV 8 1968

# INSTRUCTIONS TO DR

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

White Copy -  
Ill. Dept. of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

- Type of Well
  - Dug ☐ Bored ☐ Hole Diam. 6 in. Depth 194 ft.
  - Curb material ☐ Buried Slab: Yes ☐ No ☐
  - Driven ☐ Drive Pipe Diam. ☐ in. Depth ☐ ft.
  - Drilled ☒ Finished in Drift ☐ In Rock ☐
  - Tubular ☐ Gravel Packed ☐
  - Grout:
 

(KIND)	FROM (FT.)	TO (FT.)
- Distance to Nearest:
 

Building	<input type="checkbox"/> Ft.	Seepage Tile Field	<input type="checkbox"/>
Cess Pool	<input type="checkbox"/>	Sewer (non Cast iron)	<input type="checkbox"/>
Privy	<input type="checkbox"/>	Sewer (Cast iron)	<input type="checkbox"/>
Septic Tank	<input type="checkbox"/>	Barnyard	<input type="checkbox"/>
Leaching Pit	<input type="checkbox"/>	Manure Pile	<input type="checkbox"/>
- Well furnishes water for human consumption? Yes ☐ No ☐
- Date well completed ☐
- Permanent Pump Installed? Yes ☐ Date ☐ No ☐

Manufacturer	<input type="checkbox"/>	Type	<input type="checkbox"/>	Location	<input type="checkbox"/>
Capacity	<input type="checkbox"/> gpm.	Depth of Setting	<input type="checkbox"/>	Ft.	<input type="checkbox"/>
- Well Top Sealed? Yes ☐ No ☐ Type ☐

Pitless Adapter Installed?	Yes <input type="checkbox"/> No <input type="checkbox"/>
Manufacturer	<input type="checkbox"/>
Model Number	<input type="checkbox"/>
- How attached to casing? ☐ Yes ☐ No ☐
- Well Disinfected? Yes ☐ No ☐
- Pump and Equipment Disinfected? Yes ☐ No ☐
- Pressure Tank Size ☐ gal. Type ☐

Location	<input type="checkbox"/>
----------	--------------------------
- Water Sample Submitted? Yes ☐ No ☐

### REMARKS:

This is a test hole - #2  
Drilling completed 4/19/79

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

- Property owner Wabash Tape Corp. Well No.    
Address 221 E. Main Street, Huntley, IL 60142
- Driller William M. Boetsch License No. 92-436
- Permit No. 84233 Date 3/27/79
- Water from   13. County McHenry  
at depth   to   ft. Sec. 33  
14. Screen: Diam.   in. Twp. 43N  
Length:   ft. Slot   Rge. 7E  
Elev.


Diam. (in.)	Kind and Weight	From (ft.)	To (ft.)

SHOW LOCATION IN SECTION PLAT  
75° 4' 00" W, 35° 1' NE NE (feet 142 #2)

- Size Hole below casing:   in.
- Static level   ft. below casing top which is   ft. above ground level. Pumping level   ft. when pumping at   gpm for   hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
black loam	5	5
yellow clay	6	11
sticky blue clay	9	20
water, sand	3	23
blue clay, fine sand	10	33
water, sand	4	37
red clay, sand	4	41
gravel, sand	2	43
stone pink clay, sand	15	58

(CONTINUE ON SEPARATE SHEET IF NECESSARY) continued

SIGNED William M. Boetsch DATE 5/1/79

# INSTRUCTIONS TO DRILLER

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER, HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

White Copy -  
Ill. Dept. of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

- Type of Well
  - Dug         . Bored         . Hole Diam. 6 in. Depth 200 ft.  
Curb material         . Buried Slab: Yes          No
  - Driven         . Drive Pipe Diam.          in. Depth          ft.
  - Drilled X. Finished in Drift         . In Rock         .  
Tubular         . Gravel Packed         .
  - Grout:
 

(KIND)	FROM (FT.)	TO (FT.)
- Distance to Nearest:
 

Building <u>        </u> Ft.	Seepage Tile Field <u>        </u>
Cess Pool <u>        </u>	Sewer (non Cast iron) <u>        </u>
Privy <u>        </u>	Sewer (Cast iron) <u>        </u>
Septic Tank <u>        </u>	Barnyard <u>        </u>
Leaching Pit <u>        </u>	Manure Pile <u>        </u>
- Well furnishes water for human consumption? Yes          No
- Date well completed
- Permanent Pump Installed? Yes          Date          No
- Manufacturer          Type          Location
- Capacity          gpm. Depth of Setting          Ft.
- Well Top Sealed? Yes          No          Type
- Pitless Adapter Installed? Yes          No
- Manufacturer          Model Number
- How attached to casing?
- Well Disinfected? Yes          No
- Pump and Equipment Disinfected? Yes          No
- Pressure Tank Size          gal. Type
- Location
- Water Sample Submitted? Yes          No

### REMARKS:

This is a test hole - #1  
Drilling completed 4/3/79

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

- Property owner Wabash Tape Corp. Well No.           
Address 221 E. Main Street, Huntley, IL 60142
- Driller William M. Boetsch License No. 92-436
- Permit No. 84234 Date 3/27/79
- Water from          13. County McHenry  
at depth          to          ft. Sec. 33 19  
Screen: Diam.          in. Twp. 43N 0  
Length:          ft. Slot          Rge. 7E  
Elev.


### 15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (ft.)	To (ft.)

SHOW LOCATION IN SECTION PLAT

200' N. W. 1/4

7E

(Field #1)

- Size Hole below casing:          in.
- Static level          ft. below casing top which is          ft. above ground level. Pumping level          ft. when pumping at          gpm for          hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
top soil	5	5
brown clay	10	15
gray clay	20	35
stone gray clay	5	40
gravel	5	45
stone gray clay	15	60
gravel	32	92
pink clay	33	125
stone pink clay	40	165
gravel	10	175
gravel and shale	25	200

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Wm M. Boetsch DATE 5/3/79

FILL IN ALL PERTINENT INFORMATION REQUIRED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, ROOM 624, STATE OFFICE BUILDING, SPRINGFIELD, ILLINOIS, 62706. DO NOT DETACH GEOLOGICAL / WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

White Copy - Public Health  
Yellow Copy - Well Contractor  
Green Copy - Well Owner

ILLINOIS DEPARTMENT OF PUBLIC HEALTH  
WELL CONSTRUCTION REPORT

1. Type of Well

- a. dug \_\_\_\_\_ Bored \_\_\_\_\_ Hole Diam. \_\_\_\_\_ in. Depth \_\_\_\_\_ ft.  
Curb material \_\_\_\_\_ Buried Slab: Yes \_\_\_\_\_ No \_\_\_\_\_  
b. Driven \_\_\_\_\_ Drive Pipe Diam. \_\_\_\_\_ in. Depth \_\_\_\_\_ ft.  
c. Drilled \_\_\_\_\_ Finished in Drift \_\_\_\_\_ In Rock \_\_\_\_\_  
Tubular \_\_\_\_\_ Gravel Packed \_\_\_\_\_  
d. Grout: \_\_\_\_\_

(KIND)	FROM (Ft.)	TO (Ft.)

2. Distance to Nearest:

Building \_\_\_\_\_ Ft. Seepage Tile Field \_\_\_\_\_  
Cess Pool \_\_\_\_\_ Sewer (non Cast Iron) \_\_\_\_\_  
Privy \_\_\_\_\_ Sewer (Cast Iron) \_\_\_\_\_  
Septic Tank \_\_\_\_\_ Barnyard \_\_\_\_\_  
Leaching Pit \_\_\_\_\_ Manure Pile \_\_\_\_\_

3. Is water from this well to be used for human consumption?

- Yes \_\_\_\_\_ No \_\_\_\_\_  
4. Date well completed May 28, 1969  
5. Permanent Pump Installed? Yes \_\_\_\_\_ No \_\_\_\_\_  
Manufacturer \_\_\_\_\_ Type \_\_\_\_\_  
Capacity \_\_\_\_\_ gpm. Depth of setting \_\_\_\_\_ ft.  
6. Well Top Sealed? Yes ☒ No \_\_\_\_\_  
7. Pitless Adaptor Installed? Yes \_\_\_\_\_ No \_\_\_\_\_  
8. Well Disinfected? Yes \_\_\_\_\_ No \_\_\_\_\_  
9. Water Sample Submitted? Yes \_\_\_\_\_ No \_\_\_\_\_

REMARKS:

pump installed  
by owner

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner Oliver Hansen Well No. \_\_\_\_\_

Address \_\_\_\_\_

Driller Charlie Sigurd License No. \_\_\_\_\_

11. Permit No. \_\_\_\_\_ Date \_\_\_\_\_

12. Water from sand gravel 13. County \_\_\_\_\_

at depth 175 to 177 ft.

14. Screen: Diam. \_\_\_\_\_ in. Sec. 28

Length: \_\_\_\_\_ ft. Slot \_\_\_\_\_ in. Twp. 43N

Elev. \_\_\_\_\_ Rge. 7E

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
<u>5 in</u>	<u>15 lb. pipe</u>	<u>0</u>	<u>177</u>
	<u>youngstown</u>		

SHOW  
LOCATION IN  
SECTION PLAT  
SW NW NW

16. Size Hole below casing: 5 in.

17. Static level 27 ft. below casing top which is 15 ft. above ground level. Pumping level 42 ft. when pumping at 20 gpm for 1 hours.

18. FORMATIONS PASSED THROUGH

THICKNESS	DEPTH OF BOTTOM
<u>0-25 ft top soil</u>	
<u>5-67 pink clay</u>	
<u>67-115 sand gravel</u>	
<u>115-175 pink clay</u>	
<u>175-177 sand gravel</u>	

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Charles Sigurd DATE 18 May 1969

FILL IN ALL PERTINENT INFORMATION R. ESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, ROOM 616, STATE OFFICE BUILDING, SPRINGFIELD, ILLINOIS 62706. DO NOT DETACH GEOLOGICAL / WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

White - For Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

### 1. Type of Well

- a. Dug ☒ Bored ☒ Hole Diam. 5" in. Depth 242 ft.  
Curb material            Buried Slab: Yes ☐ No ☐
- b. Driven ☐ Drive Pipe Diam.            in. Depth            ft.  
c. Drilled ☒ Finished in Drift            In Rock ☒  
Tubular            Gravel Packed
- d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)
Mud Slurry	0	242'

### 2. Distance to Nearest:

Building 32 Ft. Seepage Tile Field 75 ft.  
Cess Pool            Sewer (non Cast iron)             
Privy            Sewer (Cast iron)             
Septic Tank 50 ft. Barnyard             
Leaching Pit            Manure Pile           

### 3. Is water from this well to be used for human consumption?

Yes ☒ No ☐

### 4. Date well completed

5. Permanent Pump Installed? Yes ☒ No ☐  
Manufacturer RED JACKET Type Submersible  
Capacity 10 gpm. Depth of setting 54 ft.

6. Well Top Sealed? Yes ☒ No ☐

7. Pitless Adaptor Installed? Yes ☒ No ☐

8. Well Disinfected? Yes ☒ No ☐

9. Water Sample Submitted? Yes ☒ No ☐

### REMARKS:

## GEOLOGICAL WATER SURVEYS WATER WELL RECORD

10. Dept. Mines and Minerals permit No. 31403 Year 74

11. Property owner KENNETH BRADLEY Well No.           

Address CARLY JR. HOMER HUNTLEY ILL 61032

Driller MARTIN J. JONES & SON License No. 102-7

12. Water from Limestone 13. County McHENRY

at depth 230 to 242 ft.

14. Screen: Diam.            in.

Length:            ft. Slot           

15. Casing and Liner Pipe 3 1/2" S 146 W Sec. 28.5A

Twp. 43N

Rng. 7E

Elev. 875

SHOW LOCATION IN SECTION PLAT

3500' FROM W. LINE OF SEC.

200' FROM N. LINE OF SEC.

16. Size Hole below casing: 4 3/4 in.

17. Static level 50 ft. below casing top which is 2 ft. above ground level. Pumping level 34 ft. when pumping at 15 gpm for 1 hours.

18.	FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
	BLACK LOAM	1	3'
	YELLOW CLAY	3	15'
	BROWN CLAY	15	30
	GREY CLAY	20	40
	RED CLAY & SAND	40	190
	GREY SAND & CLAY	190	210
	Limestone	210	342
(CONTINUE ON SEPARATE SHEET IF NECESSARY)			

SIGNED Jones, A. Hutchings DATE 13/17/74

Signature: Will Only.

4a Copy -  
- III. Dept. of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

**ILLINOIS DEPARTMENT OF PUBLIC HEALTH  
WELL CONSTRUCTION REPORT**

1. Type of Well
- a. Dug\_\_\_\_. Bored\_\_\_\_. Hole Diam. 5 in. Depth 75 ft.  
Curb material\_\_\_\_. Buried Slab: Yes\_\_\_\_ No\_\_\_\_
- b. Driven\_\_\_\_. Drive Pipe Diam. 5 in. Depth 75 ft.
- c. Drilled XX. Finished in Drift XX. In Rock\_\_\_\_.  
Tubular\_\_\_\_. Gravel Packed\_\_\_\_.
- d. Grout: \_\_\_\_\_

(KIND)	FROM (P.)	TO (P.)

2. Distance to Nearest:  
Building 25 Ft. Seepage Tile Field 80  
Cess Pool \_\_\_\_\_ Sewer (non Cast iron) \_\_\_\_\_  
Privy \_\_\_\_\_ Sewer (Cast iron) \_\_\_\_\_  
Septic Tank 90 Barnyard \_\_\_\_\_  
Leaching Pit \_\_\_\_\_ Manure Pile \_\_\_\_\_
3. Well furnishes water for human consumption? Yes XX No \_\_\_\_\_
4. Date well completed June 21, 1976
5. Permanent Pump Installed? Yes XX Date June 21 No \_\_\_\_\_  
Manufacturer Barnes Type sub Location in well  
Capacity 25 gpm. Depth of Setting 42 Type Wells  
Well Top Sealed? Yes XX No \_\_\_\_\_
6. Well Top Sealed? Yes XX No \_\_\_\_\_  
Pitless Adapter Installed? Yes XX No \_\_\_\_\_  
Manufacturer Wells Model Number \_\_\_\_\_
7. How attached to casing? U-bolt
8. Well Disinfected? Yes XX No \_\_\_\_\_
9. Pump and Equipment Disinfected? Yes XX No \_\_\_\_\_
10. Pressure Tank Size 202 gal. Type Well-X-Troll
11. Location in basement  
Water Sample Submitted? Yes XX No \_\_\_\_\_

REMARKS:

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner T. Spradlin Well No. 1  
Address Garlief Road, Huntley  
Driller Paul Barker License No. 92-563  
11. Permit No. 44959 Date February 27, 1976  
12. Water from Gravel 13. County McHenry  
Formation  
at depth 25 to 75 ft.  
14. Screen: Diam. \_\_\_\_\_ in.  
Length: \_\_\_\_\_ ft. Slot \_\_\_\_\_  
Elev. \_\_\_\_\_

Diam. (in.)	Kind and Weight	From (ft.)	To (ft.)
5	15 per. ft.	0	75

SHOW LOCATION IN SECTION PLAY  
70'n, 80'E 8 S W New

16. Size Hole below casing: 5 in.  
17. Static level 20 ft. below casing top which is 1 ft. above ground level. Pumping level 60 ft. when pumping at 25 gpm for 6 hours.

18.	FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
	Topsoil	0	3
	Clay & Gravel	3	15
	Gray Clay	15	25
	Clay & Gravel	25	70
	Gravel	70	75

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

**SIGNED**

DATE Aug, 1976

FILL IN ALL PERTINENT INFORMATION REQUIRED BY THE  
DEPARTMENT OF PUBLIC HEALTH, ROOM 616,  
ILLINOIS, 62706. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO  
PROVIDE PROPER WELL LOCATION.

White Copy - Health  
Yellow Copy - Contractor  
Blue Copy - Well Owner

# ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

## 1. Type of Well

- a. Dug 6 in. Hole Diam. 11.5 ft.  
Curb material Concrete. Buried Slab: Yes No
- b. Driven 6 in. Drive Pipe Diam. 11.5 ft.  
c. Drilled ✓. Finished in Drift ✓. In Rock ✓.  
Tubular 6 in. Gravel Packed ✓.
- d. Grout: Concrete

(KIND)	FROM (FT.)	TO (FT.)

## 2. Distance to Nearest:

Building 6.5 Ft. Seepage Tile Field 7.5  
Cess Pool 6.5 Sewer (non Cast iron) ✓  
Privy 6.5 Sewer (Cast iron) ✓  
Septic Tank 80 Barnyard 80  
Leaching Pit 100 Manure Pile 100

## 3. Is water from this well to be used for human consumption?

- Yes ✓ No ✓
4. Date well completed July 11, 1968
5. Permanent Pump Installed? Yes ✓ No ✓  
Manufacturer Submerga Type Submerga  
Capacity 24 gpm. Depth of setting 63 ft.
6. Well Top Sealed? Yes ✓ No ✓
7. Pitless Adaptor Installed? Yes ✓ No ✓
8. Well Disinfected? Yes ✓ No ✓
9. Water Sample Submitted? Yes ✓ No ✓

## REMARKS:

## GEOLOGICAL WATER SURVEYS WATER WELL RECORD

10. Dept. Mines and Minerals permit No. MF 4305 Year 1968
11. Property owner Arthur J. State Well No.  
Address Chatham Illinois 901 West 111  
Driller Charles August License No. 12-135
12. Water from Formation 13. County McHenry  
at depth 60 to 115 ft.  
14. Screen: Diam. 6 in. Length: 26.74 ft. Slot 434 in. Elev. 7E


## 15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
6	17.2 lb. pipe		

SHOW  
LOCATION IN  
SECTION PLAT  
SE S W S W

16. Size Hole below casing: 6 in.
17. Static level 38 ft. below casing top which is 2 ft. above ground level. Pumping level 52 ft. when pumping at 24 gpm for 1 hours.

18.	FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
	Black top soil	0	6 ft
	Brown clayey clay	6	4 ft
	Dark sandy shale	40	100
	Sand gravel	100	115

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Charles August DATE July 11, 1968

White Copy -  
Ill. Dep. of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

INSTRUCTIONS TO DRILLER

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH  
WELL CONSTRUCTION REPORT

1. Type of Well

- a. Dug          Bored          Hole Diam.          in. Depth          ft.  
Curb material          Buried Slab: Yes          No           
b. Driven          Drive Pipe Diam.          in. Depth          ft.  
c. Drilled          Finished in Drift          In Rock           
Tubular          Gravel Packed           
d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)
Grout	0	200

2. Distance to Nearest:

- Building          Ft. Seepage Tile Field           
Cess Pool          Sewer (non Cast iron)           
Privy          Sewer (Cast iron)           
Septic Tank          Barnyard           
Leaching Pit          Manure Pile

3. Well furnishes water for human consumption? Yes          No           
4. Date well completed

5. Permanent Pump Installed? Yes          Date          No         

Manufacturer          Type          Location in Well           
Capacity          gpm. Depth of Setting          Ft.

6. Well Top Sealed? Yes          No          Type           
7. Pitless Adapter Installed? Yes          No           
Manufacturer          Model Number

How attached to casing?           
8. Well Disinfected? Yes          No         

9. Pump and Equipment Disinfected? Yes          No         

10. Pressure Tank Size          gal. Type           
Location         

11. Water Sample Submitted? Yes          No         

REMARKS:

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner          Well No.           
Address          License No.         

Driller          Date           
11. Permit No.          13. County         

12. Water from          at depth          ft.  
Formation         

14. Screen: Diam.          in. Length:          ft. Slot          Elev.         

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
5"	Galv. Steel	0	210
	1" lb. per ft.		

16. Size Hole below casing:          in.

17. Static level          ft. below casing top which is          ft. above ground level. Pumping level          ft. when pumping at          gpm for          hours.

18.	FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
	Top Soil	25	25
	Sand & Gravel w/ some shale	100	125
	Shale	85	210
	Limestone	70	280

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED          DATE



File Copy -  
Ill. Dept. of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

# ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

## 1. Type of Well

- a. Dug        Bored        Hole Diam. 5 in. Depth 184 ft.  
Curb material        Buried Slab: Yes        No         
b. Driven        Drive Pipe Diam.        in. Depth        ft.  
c. Drilled XX Finished in Drift        In Rock         
Tubular        Gravel Packed         
d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)

## 2. Distance to Nearest:

- Building        Ft. Seepage Tile Field         
Cess Pool        Sewer (non Cast iron)         
Privy        Sewer (Cast iron)         
Septic Tank        Barnyard         
Leaching Pit        Manure Pile         
3. Well furnishes water for human consumption? Yes XX No         
4. Date well completed 5/5/76  
5. Permanent Pump Installed? Yes X Date        No         
Manufacturer Aermotor Type Sub. Location         
Capacity 10 gpm. Depth of Setting 60 Ft.  
6. Well Top Sealed? Yes XX No        Type Water-tight  
7. Pitless Adapter Installed? Yes XX No         
Manufacturer Baker Model Number SANDDY  
How attached to casing? Compression  
8. Well Disinfected? Yes XX No         
9. Pump and Equipment Disinfected? Yes XX No         
10. Pressure Tank Size 80 gal. Type MEDALIST  
Location         
11. Water Sample Submitted? Yes        No XX

## REMARKS:

# GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner Mr. Jay Locasio Well No.       

Address 1312 N. Green A-Meadow Streamwood, Ill

Driller William M. Bhetsch License No. 92-436

11. Permit No. 46800X 46028 Date 4/8/76

12. Water from Limestone 13. County McHenry

at depth 184 to 184 ft. Sec. 23

14. Screen: Diam.        in. Twp. 43N

Length:        ft. Slot        Rge. 7E

Elev.       

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)	SHOW LOCATION IN SECTION PLAT
5	PVC	1	184	NE SW SE

16. Size Hole below casing: 5 in.

17. Static level 30 ft. below casing top which is 1 ft.

above ground level. Pumping level 50 ft. when pumping at 8

gpm for        hours.

18.	FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
	Top soil	1	1
	Brown clay	11	12
	Sand and gravel	13	25
	Pink clay and gravel streaks	14.5	170
	Gray shale	10	180
	Shell rock and	1	184
	Limestone	+++	184+

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED William M. Bhetsch DATE 5/21/76

White Cap  
Bl. P  
Yellow  
Blue Cap - Well Owner

ILLINOIS DEPARTMENT OF PUBLIC HEALTH

FILL IN ALL PERTINENT INFORMATION RE-  
STATED AND MAIL ORIGINAL TO STATE  
DEPARTMENT OF PUBLIC HEALTH,  
JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER  
SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH  
WELL CONSTRUCTION REPORT

1. Type of Well

- a. Dug        Bored        Hole Diam. 5 in. Depth 75 ft.  
Curb material        Buried Slab: Yes No  
b. Driven        Drive Pipe Diam.        in. Depth        ft.  
c. Drilled X Finished in Drift        In Rock         
Tubular        Gravel Packed         
d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)

2. Distance to Nearest:

- Building        Ft. Seepage Tile Field         
Cess Pool        Sewer (non Cast Iron)         
Privy        Sewer (Cast Iron)         
Septic Tank        Barnyard         
Leaching Pit        Manure Pile

3. Well furnishes water for human consumption? Yes X No       

4. Date well completed 10/30/79

5. Permanent Pump Installed? Yes X Date 11/2/79 No         
Manufacturer Aermotor Type sub Location         
Capacity 12 gpm. Depth of Setting 40 Ft.

6. Well Top Sealed? Yes X No        Type         
Pitless Adapter Installed? Yes X No        Model Number snappy

7. How attached to casing? compression

8. Well Disinfected? Yes X No       

9. Pump and Equipment Disinfected? Yes X No       

10. Pressure Tank Size 42 gal. Type captivie air  
Location       

11. Water Sample Submitted? Yes        No X

REMARKS:

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner Kenco Enterprises Well No.         
Address 4619 Linden, Crystal Lake, IL 60014  
Driller William M. Boetsch License No. 92-436  
Permit No. 84661 Date 4/16/79  
11. Water from Gravel 13. County McHenry

- at depth 35 to 75 ft. Sec. 24  
14. Screen: Diam. 5 in. Twp. 43N  
Length: 5 ft. Slot 20 Rge. 8E  
Elev.

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
<u>5</u>	<u>PVC</u>	<u>1</u>	<u>70</u>

SHOW  
LOCATION IN  
SECTION PLAT  
lot # 385 front  
valley NW

16. Size Hole below casing: 5 in.  
17. Static level 15 ft. below casing top which is 1 ft.  
above ground level. Pumping level 40 ft. when pumping at 25  
gpm for 2 hours.

FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>black loam</u>	<u>8</u>	<u>8</u>
<u>gravel, sand</u>	<u>10</u>	<u>18</u>
<u>find sand</u>	<u>17</u>	<u>35</u>
<u>gravel</u>	<u>40</u>	<u>75</u>

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Wm M. Boetsch DATE 11/5/79

**WATER WELL SEALING FORM**

ILLINOIS DEPARTMENT OF PUBLIC HEALTH  
DIVISION OF ENVIRONMENTAL HEALTH  
525 WEST JEFFERSON STREET  
SPRINGFIELD, ILLINOIS 62761

RETURN ALL COPIES  
TO IDPH

**TYPE OR PRESS FIRMLY**

This form shall be submitted to this Department not more than 30 days after a potable water well, boring or monitoring well is sealed. Such wells are to be sealed not more than 30 days after they are abandoned in accordance with the sealing requirements in the Water Well Construction Code.

1. Ownership (Name of Controlling Party) U.S. Dismantelment

2. Well

Location: 8208 Miller Rd. Crystal Lake, IL McHenry County  
Address - Lot Number City County

General Description: Section 24.1e Township 43N (N)(S) Range 7E (E)(W)  
SE Quarter of the SE Quarter of the NE Quarter

3. Year Drilled unknown

4. Drilling Permit No.(and date, if known) unknown

5. Type of Well: Bored \_\_\_\_\_ Drilled XXX Other \_\_\_\_\_

6. Total Depth 180' Diameter (inches) 5"

7. Formation clear of obstruction XXXXXX yes

8. DETAILS OF PLUGGING

Filled with Pea Gravel from 180 to 80 ft.  
(cement or other materials)

Kind of plug Cement from 80 to 10 ft.

Filled with \_\_\_\_\_ from \_\_\_\_\_ to \_\_\_\_\_ ft.

Kind of plug \_\_\_\_\_ from \_\_\_\_\_ to \_\_\_\_\_ ft.

Filled with \_\_\_\_\_ from \_\_\_\_\_ to \_\_\_\_\_ ft.

Kind of plug \_\_\_\_\_ from \_\_\_\_\_ to \_\_\_\_\_ ft.

9. CASING RECORD

Upper 3 feet of casing removed XXXX Yes \_\_\_\_\_ No

If well casing consists of brick, stone, concrete blocks, porous tile, or other porous material, casing was removed to a depth of 10 feet below the surface Yes No.

10. Date well was sealed: Month March Day 2 Year 1989.

11. Licensed water well driller or other person approved by the Department performing well sealing:

K & K Well Drilling Inc. 102-000841  
Name Complete License Number  
701 First St. Batavia, IL 60510  
Address City State/Zip

White Copy -  
Ill. Dept. of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

1' RUN JNS TO DRILLERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE  
DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST  
JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER  
SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

### 1. Type of Well

- a. Dug        Bored        Hole Diam. 5 in. Depth        ft.  
Curb material        Buried Slab: Yes        No         
b. Driven        Drive Pipe Diam. 5 1/2 in. Depth 100 ft.  
c. Drilled        Finished in Drift        In Rock         
Tubular        Gravel Packed         
d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)

### 2. Distance to Nearest:

- Building 20 Ft. Sewage Tile Field         
Cess Pool        Sewer (non Cast iron)         
Privy        Sewer (Cast iron)         
Septic Tank 60 Barnyard         
Leaching Pit        Manure Pile

3. Well furnishes water for human consumption? Yes        No         
4. Date well completed         
5. Permanent Pump Installed? Yes        Date        No         
Manufacturer SEARS Type SUB Location WELL  
Capacity 8 gpm. Depth of Setting 40 Ft.  
6. Well Top Sealed? Yes        No        Type         
7. Pitless Adapter Installed? Yes        No        Model Number SPRS  
Manufacturer METALL Location WELL  
How attached to casing? Yes        No         
8. Well Disinfected? Yes        No         
9. Pump and Equipment Disinfected? Yes        No         
10. Pressure Tank Size 42 gal. Type FAIR  
Location GAS M.E.V.  
11. Water Sample Submitted? Yes        No

REMARKS:

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner Jim Bojarzik Well No.         
Address Hagers Bend Agency  
Driller Wayne Brynoff License No. 402-213  
11. Permit No. 2868 Date 9-30-76  
12. Water from ROCK 13. County McHenry  
at depth        to        ft. Sec. 24.44  
14. Screen: Diam.        in. Twp. 432  
Length:        ft. Slot        Rge. 7E  
Elev.

### 15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
5"	BLK 75/Ft	0	98

SHOW  
LOCATION IN  
SECTION PLAT  
NW NW NE

16. Size Hole below casing: 4 3/4 in.

17. Static level 20 ft. below casing top which is 1 ft.  
above ground level. Pumping level 20 ft. when pumping at 8  
gpm for 1 hours.

18.	FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
	OVER Borden	98	98
	ROCK	2	100

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Wayne Brynoff DATE 8-29-78

White Copy -  
 Dept. of Public Health  
 Blue Copy - Well Contractor  
 Blue Copy - Well Owner

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILL. 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

# ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

- Type of Well
  - Dug         . Bored         . Hole Diam. 5 in. Depth 295 ft.  
 Carb material         . Buried Slab: Yes          No
  - Driven         . Drive Pipe Diam.          in. Depth          ft.
  - Drilled X. Finished in Drift         . In Rock X.
  - Tubular         . Gravel Packed         .
- Grout:
 

(KIND)	FROM (Ft.)	TO (Ft.)
Cuttings		

- Distance to Nearest:
 

Building <u>        </u> Ft.	Seepage Tile Field <u>        </u>
Cess Pool <u>        </u>	Sewer (non Cast Iron) <u>        </u>
Privy <u>        </u>	Sewer (Cast Iron) <u>        </u>
Septic Tank <u>        </u>	Barnyard <u>        </u>
Leaching Pit <u>        </u>	Manure Pile <u>        </u>
- Well furnishes water for human consumption? Yes X No
- Date well completed December 30, 1978
- Permanent Pump Installed? Yes X No           
 Manufacturer Wellpoint Type Sub Location Well  
 Capacity          gal. Depth of Setting 130 ft.  
 Well Top Sealed? Yes X No          Type Cap  
 Pitless Adapter Installed? Yes X No           
 Manufacturer Williams Model Number B 50 AC  
 How attached to casing? Permanent
- Well Disinfected? Yes X No
- Pump and Equipment Disinfected? Yes X No           
 Pressure Tank Size 22 gal. Type Con. wire  
 Location Basement
- Water Sample Submitted? Yes          No X

REMARKS: Owner instructed.  
Well was chlorinated

# GEOLOGICAL AND WATER SURVEYS WELL RECORD

- Property owned Lawrence Noble Well No.           
 Address 1712 Pleasant St., McHenry, Ill.
- Driller James Knerim License No. 4023-27  
 Permit No. 73677 Date 4/28/78
- Water from Rock 13. County McHenry  
 at depth 20 to 295 ft. Sec. 24.50  
 Screen: Diam.          in. Twp. 43N  
 Length:          ft. Slot          Rge. 7E  
 Elev.

Diam. (in.)	Size and Weight	From (Ft.)	To (Ft.)
5"	GVC	0	199

- Size Hole below casing: 5 in.
- Static level 70 ft. below casing top which is          ft. above ground level. Pumping level 80 ft. when pumping at          gpm for          hours.

FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Top Soil	0	2
Clay	2	42
Sandy Gravel	42	47
Clay	47	142
Sandy Gravel	142	175
Clay	175	199
Shale	199	275
Rock	275	295

(CONTINUE ON SEPARATE SHEET IF NECESSARY)  
 SIGNED James Knerim DATE 10/18/79

FILL IN ALL PERTINENT INFORMATION REQUESTED MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, ROOM 615, STATE OFFICE BUILDING, SPRINGFIELD, ILLINOIS, 62706. DO NOT DETACH GEOLOGICAL / WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

White Copy - Ill. Dept. of Pub. Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

### 1. Type of Well

- a. Dug ☐ Bored ☐ Hole Diam.        in. Depth        ft.  
Curb material        Buried Slab: Yes ☐ No ☐  
b. Driven ☐ Drive Pipe Diam. 3 in. Depth 172 ft.  
c. Drilled ☒ Finished in Drift ☒ In Rock ☐  
Tubular        Gravel Packed         
d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)

### 2. Distance to Nearest:

- Building 5 Ft. Seepage Tile Field 100  
Cess Pool        Sewer (non Cast iron)         
Privy        Sewer (Cast iron)         
Septic Tank 75 Barnyard         
Leaching Pit        Manure Pile

### 3. Is water from this well to be used for human consumption?

Yes ☒ No ☐

4. Date well completed 12/14/71  
5. Permanent Pump Installed? Yes ☒ No ☐  
Manufacturer ASUZ Type Submersible  
Capacity 12 gpm. Depth of setting 130 ft.  
6. Well Top Sealed? Yes ☒ No ☐  
7. Pitless Adaptor Installed? Yes ☒ No ☐  
8. Well Disinfected? Yes ☒ No ☐  
9. Water Sample Submitted? Yes ☐ No ☒

### REMARKS:

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner Ray Piets Well No.         
Address Elgashauer Rd., Huntley  
Driller Peter Piets License No. 92-73  
11. Permit No. 13299 Date         
12. Water from Gravelly Sand 13. County McHenry  
at depth 172 to        ft.  
14. Screen: Diam. 4 3/4 in.  
Length: 7 1/2 ft. Slot        Elev.

Sec. <u>24.58</u>									
Twp. <u>43N</u>									
Rge. <u>7E</u>									
Elev. <u>      </u>									

### 15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
<u>5</u>	<u>Galv-15 lbs</u>	<u>0</u>	<u>272</u>

SHOW LOCATION IN SECTION PLAT

NE SE SW

16. Size Hole below casing: 5 in.  
17. Static level 50 ft. below casing top which is        ft. above ground level. Pumping level 65 ft. when pumping at 25 gpm for 3 hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>Sand &amp; Gravel</u>	<u>60</u>	<u>60</u>
<u>Sandy Red Clay &amp; Gravel</u>	<u>23</u>	<u>83</u>
<u>Sand &amp; Gravel</u>	<u>35</u>	<u>118</u>
<u>Red Clay, Sand &amp; Gravel</u>	<u>22</u>	<u>143</u>
<u>Sand &amp; Gravel</u>	<u>27</u>	<u>170</u>
<u>Coarse Brown Sand</u>	<u>2</u>	<u>172</u>

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED John Piets DATE 12/30/71

1. In. of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

FILL IN ALL PERTINENT INFO AT REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

# ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

## 1. Type of Well

- a. Dug    Bored    Hole Diam 5 in. Depth 28 ft.  
Curb material    Buried Slab: Yes    No     
b. Driven    Drive Pipe Diam. 5 in. Depth 28 ft.  
c. Drilled    Finished in Drift    In Rock     
Tubular    Gravel Packed     
d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)

## 2. Distance to Nearest:

- Building 35 Ft. Seepage Tile Field     
Cess Pool    Sewer (non Cast iron)     
Privy    Sewer (Cast iron)     
Septic Tank 100 Barnyard     
Leaching Pit    Manure Pile     
Well furnishes water for human consumption? Yes    No

## 3. Well completed 10-30-77

4. Date well completed 10-30-77  
5. Permanent Pump Installed? Yes    No    Date 10-31-77  
Manufacturer STA Rite Type SUB Location WELL  
Capacity 8 gpm. Depth of Setting 80 ft.  
6. Well Top Sealed? Yes    No    Type CAP  
7. Pitless Adapter Installed? Yes    No    Model Number SPH 5  
Manufacturer Mecell Bolt on

- How attached to casing?    No     
8. Well Disinfected? Yes    No

9. Pump and Equipment Disinfected? Yes    No

10. Pressure Tank Size 8 gal. Type CON AIR  
Location BASE ment

11. Water Sample Submitted? Yes    No

## REMARKS:

# GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner John Spinolas Well No.   

Address CRYSTAL LAKE

Driller W. Burgess License No. 102-217

Permit No. 67-337 Date 9-28-77

12. Water from GRAVEL 13. County Mc Henry

at depth 28 to 28 ft. Sec. 24

14. Screen: Diam.    in. Twp. 43

Length:    ft. Slot    Rge.   

Elev.   

15. Casing and Liner Pipe

Diam. (In.)	Kind and Weight	From (Ft.)	To (Ft.)
<u>5</u>	<u>BLK 5/8</u>	<u>0</u>	<u>128</u>

SHOW LOCATION IN SECTION PLAT  
SE NW NW

16. Size Hole below casing: 6 INCH in.

17. Static level 40 ft. below casing top which is    ft.

above ground level. Pumping level 40 ft. when pumping at    gpm for    hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>OVER BURDEN</u>	<u>128</u>	<u>128</u>
<u>WATER BEARING</u>	<u>128</u>	
<u>GRAVEL</u>		

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Wayne August DATE 2-2-79

White County  
Ill. Dept. of  
Health  
Well Owner  
Well Contractor

FILL IN ALL PERTINENT INFORMATION REQUIRED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, ROOM 1000, 1000 N. SPRINGFIELD, ILLINOIS, 62706. DO NOT DETACH GEOLOGICAL / WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH  
WELL CONSTRUCTION REPORT

1. Type of Well  
a. Dug    Bored    Hole Diam. 5 in. Depth 275 ft.  
Curb material    Buried Slab: Yes    No     
b. Driven    Drive Pipe Diam.    in. Depth    ft.  
c. Drilled XX Finished in Drift    In Rock     
Tubular    Gravel Packed     
d. Grout: 

(KIND)	FROM (Ft.)	TO (Ft.)
2. Distance to Nearest:  
Building 20 Ft. Seepage Tile Field     
Cess Pool    Sewer (non Cast Iron)     
Privy    Sewer (Cast Iron)     
Septic Tank 75 Barnyard     
Leaching Pit    Manure Pile
3. Is water from this well to be used for human consumption?  
Yes XX No
4. Date well completed Feb. 15, 1972
5. Permanent Pump Installed? Yes XX No     
Manufacturer Barns Type Subb  
Capacity 10 gpm. Depth of setting 125 ft.
6. Well Top Sealed? Yes    No
7. Pitless Adaptor Installed? Yes    No
8. Well Disinfected? Yes XX No
9. Water Sample Submitted? Yes XX No

REMARKS:

IDPH 4.065  
10/68

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner Gary IGrau Well No. 1  
Address Halliguis Road Huntly, Ill.  
Driller Paul Barker License No. 22-563  
11. Permit No. 013170 Date Dec. 2, 1971  
12. Water from ECGVC L 13. County McHenry  
at depth 20 to 23 ft. Sec. S 20  
14. Screen: Diam. 4 3/4 in. Twp. 43n  
Length:    ft. Slot 7E Rge.    Elev.     
15. Casing and Liner Pipe  

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
<u>5"</u>	<u>1.5 lb Galv.</u>	<u>0</u>	<u>275</u>

SHOW LOCATION IN SECTION PLAT  
100' N 80' W SE 1/4  
SE NW NE

 16. Size Hole below casing: 5 in. 17. Static level 5 ft. below casing top which is 1 ft. above ground level. Pumping level 75 ft. when pumping at 20 gpm for 1 hours. |

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
L Top Soil	0-25	25
Calay	25-165	165
Red Clay	165-205	205
Sand	205-235	235
Gravel	235-275	275

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Paul Barker DATE 2-5-72  
Barker Drilling Co.



Blue Copy -  
Ill. Dept. of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

INSTR. FORM NO. 10-1-68

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, ROOM 616, STATE OFFICE BUILDING, SPRINGFIELD, ILLINOIS, 62706. DO NOT DETACH GEOLOGICAL / WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH  
WELL CONSTRUCTION REPORT

1. Type of Well

- a. Dig 4 in. Bored 4 in. Hole Diam. 4 in. Depth 195 ft.  
Curb material Concrete Buried Slab: Yes No  
b. Driven 4 in. Drive Pipe Diam. 4 in. Depth 195 ft.  
c. Drilled X Finished in Drift Yes In Rock X  
Tubular Yes Gravel Packed Yes  
d. Grout: Yes

(KIND)	FROM (FT.)	TO (FT.)
Gravel Slurry	0	191

2. Distance to Nearest:

- Building 75 ft. Seepage Tile Field 75 ft.  
Cess Pool 75 ft. Sewer (non Cast iron) 75 ft.  
Privy 75 ft. Sewer (Cast iron) 75 ft.  
Septic Tank 50 ft. Barnyard 75 ft.  
Leaching Pit 75 ft. Manure Pile 75 ft.

3. Is water from this well to be used for human consumption?

- Yes X No No  
4. Date well completed 8/23/74  
5. Permanent Pump Installed? Yes X No No  
Manufacturer Ken Jacket Type Submersible  
Capacity 12 gpm. Depth of setting 105 ft.  
6. Well Top Sealed? Yes X No No  
7. Pitless Adaptor Installed? Yes X No No  
8. Well Disinfected? Yes X No No  
9. Water Sample Submitted? Yes X No No

REMARKS:

IDPH 4.065  
10/68

GEOLOGICAL AND WATER SURVEYS WELL RECORD

(Arthur Stutevant)

10. Property owner Nest Haven Blues Well No. 102-7  
Address HALIGAS RD  
Driller MARTIN WILSON License No. 102-7  
Permit No. 27610 Date 2/13/74  
11. Water from Rock (Silurian) 13. County Ma Henry  
at depth 151 to 195 ft. Sec. 15.35  
14. Screen: Diam. 4 in. Slot 1/8 in. Twp. 43N  
Length: 4 ft. Slot 1/8 in. Rge. 7E  
Elev. 370

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
4"	Galv	0	191

SHOW  
LOCATION IN  
SECTION PLAT  
SW SW NE

16. Size Hole below casing: 4 in.

17. Static level 20 ft. below casing top which is 2 ft. above ground level. Pumping level 105 ft. when pumping at 12 gpm for 1 hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
YELLOW CLAY	0-20'	
SAND & GRAVEL	20-30'	
GRAVEL SAND & CLAY	30-40'	
FINE SAND & GRAVEL	40-45'	
CLAY SAND & CLAY GRAVEL	45-170'	
SAND & GRAVEL	170-185'	
GRAY SAND-CLAY GRAVEL	185-191'	
GRAY Limestone Bedrock	191-195'	

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED James Hutchings DATE 11/26/74

Write Copy -  
Ill. Dept. of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

INSTRUCTIONS TO DRILLERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, ROOM 616, STATE OFFICE BUILDING, SPRINGFIELD, ILLINOIS, 62706. DO NOT DETACH GEOLOGICAL / WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH  
WELL CONSTRUCTION REPORT

1. Type of Well
- a. Dug 4 ft. Bored 4 in. Hole Diam. 4 in. Depth 174 ft.  
Curb material           . Buried Slab: Yes    No
- b. Driven           . Drive Pipe Diam.            in. Depth            ft.
- c. Drilled X. Finished in Drift X. In Rock           .  
Tubular           . Gravel Packed           .
- d. Grout:

(KIND)	FROM (FT.)	TO (FT.)
MUD SLURRY	0	165

2. Distance to Nearest:
- Building            Ft. Seepage Tile Field 75 ft.  
Cess Pool            Sewer (non Cast iron)             
Privy            Sewer (Cast iron)             
Septic Tank 50 ft. Barnyard             
Leaching Pit            Manure Pile
3. Is water from this well to be used for human consumption?  
Yes X No

4. Date well completed 2/18/74
5. Permanent Pump Installed? Yes X No             
Manufacturer RED JACKET Type Submersible  
Capacity 15 gpm. Depth of setting 63 ft.
6. Well Top Sealed? Yes X No
7. Pitless Adaptor Installed? Yes X No
8. Well Disinfected? Yes            No
9. Water Sample Submitted? Yes X No

REMARKS:

IDPH 4.065  
10/68

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner West Haven Oaks Well No.             
Address (Boyle)  
Driller MARVIN WILKES & SON License No. 102-7  
Permit No. 19184 Date 6/27/73  
11. Water from GRAVEL 13. County MAHENRY  
at depth 46.5 to 174 ft. Sec. 15  
14. Screen: Diam.            in. Twp. 43N  
Length:            ft. Slot            Rge. 7E  
Elev. 370


SHOW  
LOCATION IN  
SECTION PLAT

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
4"	GAUL.		

SHOW  
LOCATION IN  
SECTION PLAT

16. Size Hole below casing: 4 in.

17. Static level 10 ft. below casing top which is 2 ft.  
above ground level. Pumping level 63 ft. when pumping at 15 gpm for 1 hours.

FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
BLK LOAM	0-1'	
VEL CLAY	1-2'	
BLUE CLAY	2-5'	
SAND & GRAVEL	5-15'	
BLUE CLAY	15-20'	
SAND & GRAVEL	20-25'	
BROWN CLAY	25-27'	
SAND & GRAVEL	27-32'	
BROWN SAND & CLAY	32-140'	
SAND	140-150'	
BROWN CLAY	150-165'	
GRAVEL	160-174'	

(CONTINUE ON SEPARATE SHEET IF NECESSARY)


SIGNED James Mutchings DATE 11/26/74

# Well Construction Report

THIS FORM MUST BE COMPLETED WITHIN 30 DAYS  
OF WELL COMPLETION AND SENT TO  
THE ILLINOIS DEPARTMENT OF PUBLIC HEALTH  
DIVISION OF ENVIRONMENTAL HEALTH  
525 WEST JEFFERSON STREET  
SPRINGFIELD, ILLINOIS 62761

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

9. Driller MARK NEELY License No. 2444  
10. Well Site Address 18 AT 47 HUNTER  
11. Property Owner JAMES VEUGLER Well No. \_\_\_\_\_  
12. Permit No. 006571 Date Issued 10-7-88  
13. Location: County Mc HENRY  
Sec. 16.50  
Twp. 43N  
Rge. 7E



14. Water from LIME at depth 176 ft  
15. Casing and Liner Pipe to 192 ft  
Diam. (in) Kind and Weight From (ft) To (ft) Show location in section plat

SE NE SW

5"	SDR-21-200	+2	182	
	PVC CASING			

16. Screen: Diam. \_\_\_\_\_ in, Length \_\_\_\_\_ in, Slot Size \_\_\_\_\_  
17. Size hole below casing 5 in. 18. Ground Elev. \_\_\_\_\_ ft msl.  
19. Static level 5 ft below casing top which is ±2 ft. above ground level. Pumping level 20 ft, pumping gpm for 2 hours.

20. Earth Materials Passed Through		Depth of	
		Top	Bottom
Top Soil		2	2
Brown Clay		22	24
Fine Gravel		6	30
Brown Clay		140	170
Gravel		6	176
GREEN LIME		6	182

Continue on separate sheet if necessary.

Signed James Veugler Date 3-2-89

1. Type of Well  
a. Bored \_\_\_\_\_ Hole Diam. 5 in. Depth 182 ft  
Buried Slab: Yes \_\_\_\_\_ No \_\_\_\_\_  
b. Driven \_\_\_\_\_ Drive Pipe Diam. 5 in. Depth 182 ft  
c. Drilled \_\_\_\_\_ Finished in Drift \_\_\_\_\_ In Rock ✓  
d. Grout: (KIND) FROM (Ft.) TO (Ft.)  
Mud +2 182

2. Well furnishes water for human consumption? Yes ✓ No \_\_\_\_\_  
3. Date well drilled 12-19-88  
4. Permanent pump installed? Yes \_\_\_\_\_ Date \_\_\_\_\_ No \_\_\_\_\_  
Manufacturer \_\_\_\_\_ Type \_\_\_\_\_

Location \_\_\_\_\_  
Capacity \_\_\_\_\_ gpm. Depth of setting \_\_\_\_\_ ft.  
5. Well top sealed? Yes ✓ No \_\_\_\_\_ Type Gravel  
6. Pitless adapter installed? Yes \_\_\_\_\_ No \_\_\_\_\_  
Manufacturer \_\_\_\_\_ Model No. \_\_\_\_\_

How attached to casing? \_\_\_\_\_  
7. Well disinfected? Yes ✓ No \_\_\_\_\_  
8. Pump and equipment disinfected? Yes ✓ No \_\_\_\_\_  
Pump By Others!

### IMPORTANT NOTICE

This State Agency is requesting disclosure of information that is necessary to accomplish the statutory purpose as outlined under Public Act 85-0863. Disclosure of this information is mandatory. This form has been approved by the Forms Management Center.

PRESS FIRMLY WITH BLACK PEN OR TYPE

Do Not Use Felt Pen

INSTRUCTIONS TO DRILLERS

FILL IN ALL PERTINENT INFORMATION. ON REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH  
WELL CONSTRUCTION REPORT

GEOLOGICAL AND WATER SURVEYS WELL RECORD

1. Type of Well

- a. Dug ☐ Bored ☐ Hole Diam. 5 in. Depth 215 ft.  
Curb material ☐ Buried Slab: Yes ☐ No ☐  
b. Driven ☐ Drive Pipe Diam. ☐ in. Depth ☐ ft.  
c. Drilled ☒ Finished in Drift ☐ In Rock ☒  
Tubular ☐ Gravel Packed ☐  
d. Grout: ☐

(KIND)	FROM (Ft.)	TO (Ft.)
Cuttings	9	206

2. Distance to Nearest:

- Building 20 Ft. Seepage Tile Field ☐  
Cess Pool ☐ Sewer (non Cast Iron) ☐  
Privy ☐ Sewer (Cast Iron) ☐  
Septic Tank 75 Barnyard ☐  
Leaching Pit ☐ Manure Pile ☐  
3. Well furnishes water for human consumption? Yes ☒ No ☐

4. Date well completed 6/8/84  
5. Permanent Pump Installed? Yes ☒ Date 6/8/84 No ☐  
Manufacturer Red Jacket Subm Location in well 120 Ft.  
Capacity 15 gpm. Depth of Setting 120 Type Williams Cap  
6. Well Top Sealed? Yes ☒ No ☐ Type Williams Cap  
7. Pitless Adapter Installed? Yes ☒ No ☐  
Manufacturer Williams Model Number B50AC  
How attached to casing? Locknut  
8. Well Disinfected? Yes ☒ No ☐  
9. Pump and Equipment Disinfected? Yes ☒ No ☐  
10. Pressure Tank Size ☐ gal. Type None  
Location ☐

11. Water Sample Submitted? Yes ☐ No ☒  
REMARKS:  
Owner instructed to take sample.  
Hooked system to existing tank.

10. Property owner Charles Ernesti Well No. ☐  
Address Ernesti Road Huntley  
Driller Marvin Nice License No. 102 00458  
Permit No. 112713 Date 6/4/84  
11. Water from Limestone 13. County McHenry  
at depth 206 to 215 ft.  
14. Screen: Diam. ☐ in. Sec. 17.7a  
Length: ☐ ft. Slot ☐ in. Twp. 43N  
Rge. 7E  
Elev. ☐

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
5"	Black Steel	0	206
	15 lbs per ft		

16. Size Hole below casing: 5 in.  
17. Static level 45 ft. below casing top which is 1 ft. above ground level. Pumping level 45 ft. when pumping at 10 gpm for 4 hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Surface & <del>Early</del> Clay	80	80
Sand & Gravel	40	120
Clay	86	206
Limestone	9	215

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Marvin Nice DATE 1/21/85

FILL IN ALL PERTINENT INFORMATION REQUIRED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

White Copy - Well Owner  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

## ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

- Type of Well
  - Dug ☐ Bored ☐ Hole Diam. 5 in. Depth 220 ft.  
Curb material ☐ Buried Slab: Yes ☐ No ☐
  - Driven ☐ Drive Pipe Diam. ☐ in. Depth ☐ ft.
  - Drilled ☒ Finished in Drift ☐ In Rock ☐  
Tubular ☐ Gravel Packed ☐
  - Grout:
 

(KIND)	FROM (FT.)	TO (FT.)
- Distance to Nearest:
 

Building <input type="checkbox"/> Ft.	Seepage Tile Field <input type="checkbox"/>
Cess Pool <input type="checkbox"/>	Sewer (non Cast iron) <input type="checkbox"/>
Privy <input type="checkbox"/>	Sewer (Cast iron) <input type="checkbox"/>
Septic Tank <input type="checkbox"/>	Barnyard <input type="checkbox"/>
Leaching Pit <input type="checkbox"/>	Manure Pile <input type="checkbox"/>
- Well furnishes water for human consumption? Yes ☒ No ☐
- Date well completed 12/11/75
- Permanent Pump Installed? Yes ☒ No ☐
- Manufacturer Aermator Type sub Location    
Capacity 10 gpm. Depth of Setting 160 Ft.
- Well Top Sealed? Yes ☒ No ☐ Type Water tight
- Pitless Adapter Installed? Yes ☒ No ☐  
Manufacturer Blaser Model Number Snapppy  
How attached to casing? Compression
- Well Disinfected? Yes ☒ No ☐
- Pump and Equipment Disinfected? Yes ☒ No ☐
- Pressure Tank Size 80 gal. Type post-pressure  
Location
- Water Sample Submitted? Yes ☐ No ☒

REMARKS:

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

- Property owner John Riedle Well No.    
Address 824 Augusta Ave., Elgin, Ill. 60120
- Driller Boetsch Water Supply License No. 92-436
- Permit No. 40516 Date 8/26/75
- Water from Limestone 13. County Madison McHenry  
at depth 202 to 220 ft.  
14. Screen: Diam.   in. Sec. 19 Twp. 43N  
Length:   ft. Slot   in. Rge. 7E  
Elev.


### 15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (ft.)	To (ft.)
5	PVC	1	202

SHOW LOCATION IN SECTION PLAT

N E N E N E

- Size Hole below casing: 5 in.
- Static level 80 ft. below casing top which is 1 ft. above ground level. Pumping level 120 ft. when pumping at 8 gpm for 2 hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Top Soil	1	1
Brown c lay	15	16
Pink clay and gravel	64	80
Streaks varying from 2-4' in thickness		
Pink stonev clay	100	180
Shell rock and shale	22	202
Bl. white Limestone	18	220

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED   DATE 9/13/76

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

White Copy -  
Ill. Dept. of Public Health  
Yellow Copy - Well Contractor  
Blue Copy - Well Owner

# ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

- Type of Well
  - Dug         . Bored         . Hole Diam. 5 in. Depth 235 ft.  
Curb material         . Buried Slab: Yes No
  - Driven         . Drive Pipe Diam.          in. Depth          ft.
  - Drilled XX. Finished in Drift         . In Rock         .  
Tubular         . Gravel Packed         .
  - Grout:

(KIND)	FROM (Ft.)	TO (Ft.)

- Distance to Nearest:
  - Building          Ft.
  - Cess Pool
  - Privy
  - Septic Tank
  - Leaching Pit
  - Well furnishes water for human consumption? Yes x No
- Date well completed 3/30/77
- Permanent Pump Installed? Yes x Date
- Manufacturer Baker-Monitor Type Aeromob Location
- Capacity 10 gpm. Depth of Setting 80 Ft.
- Well Top Sealed? Yes x No          Type watertite
- Pitless Adapter Installed? Yes x No
- Manufacturer Baker-Monitor Model Number snappy
- How attached to casing?          compression
- Well Disinfected? Yes x No
- Pump and Equipment Disinfected? Yes x No
- Pressure Tank Size 60 gal. Type Medalist
- Location
- Water Sample Submitted? Yes          No x

REMARKS:

## GEOLOGICAL AND WATER SURVEYS WELL RECORD

- Property owner Marvin Moody Well No.           
Address 110 Park Blvd. Streamwood, Ill.
- Driller William M. Boetsch License No. 92-436
- Permit No. 49285 Date 7/8/76
- Water from Limestone 13. County McHenry  
at depth 226 to 235 ft.  
14. Screen: Diam.          in.  
Length:          ft. Slot          Elev.

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
5	PVC	1	216

SHOW LOCATION IN SECTION PLAT: NE SE SE

- Size Hole below casing: 5 in.
- Static level 60 ft. below casing top which is 1 ft. above ground level. Pumping level 70 ft. when pumping at 8 gpm for 2 hours.

FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Top soil	2	2
Brown clay	8	10
Bray clay	20	30
Pink clay	30	60
Stoney clay	50	110
Pink shale	10	150
Broken limestone and shale	66	216
Limestone and water	10	226
Limestone, water, and shale	9	235

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED William Boetsch DATE 4/5/77

FILL IN ALL PERTINENT INFORMATION REQUIRES. DO NOT MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

# ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

## 1. Type of Well

- a. Dug ☒ Bored ☒ Hole Diam. 7-7/8 Depth 168 ft.  
Curb material            Buried Slab: Yes ☒ No ☒  
b. Driven ☒ Drive Pipe Diam. 5 in. Depth 168 ft.  
c. Drilled ☒ Finished in Drift ☒ In Rock ☒  
Tubular ☒ Gravel Packed ☒

(KIND)	FROM (Ft.)	TO (Ft.)
Drilling		
Mud	0	160

## 2. Distance to Nearest:

- Building 15 Ft. Seepage Tile Field 75  
Cess Pool            Sewer (non Cast iron)             
Privy            Sewer (Cast iron)             
Septic Tank 75 Barnyard             
Leaching Pit            Manure Pile

3. Well furnishes water for human consumption? Yes ☒ No ☒  
4. Date well completed 5/30/79  
5. Permanent Pump Installed? Yes ☒ Date 8/17/79 No ☒  
Manufacturer Red Jacket Type sub Location         
Capacity 15 gpm. Depth of Setting 50 Ft.  
6. Well Top Sealed? Yes ☒ No ☒ Type             
7. Pitless Adapter Installed? Yes ☒ No ☒  
Manufacturer Moniflor Model Number Snappy  
How attached to casing? u.c.lamp  
8. Well Disinfected? Yes ☒ No ☒  
9. Pump and Equipment Disinfected? Yes ☒ No ☒  
10. Pressure Tank Size 202 gal. Type Well-x-trol  
Location

11. Water Sample Submitted? Yes ☒ No ☒

## REMARKS:

# GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner John J. Fettes Well No.             
Address Coyne Station Rd, Huntley  
Driller William uemann License No. 102-142  
Permit No. 79591 Date 9/19/78  
11. Water from Gravel 13. County McHenry  
at depth 160 to 168 ft.  
12. Screen: Diam. 5 in.  
Length: 4 ft. Slot 30  
Sec. 192b  
Twp. 43N  
Rge. 7E  
Elev.


## 15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
5	200 lb PVC	0	164

SHOW  
LOCATION IN  
SECTION PLAT  
NW SE SE

16. Size Hole below casing: 7-7/8 in.

17. Static level 28 ft. below casing top which is 2 ft. above ground level. Pumping level 30 ft. when pumping at 35 gpm for 4 hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Clay & Gravel	20	20
Clay	140	160
Gravel	8	168

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED William Fettes DATE 5-24-79